

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JEFFREY H. MICHAEL
Lease or Property Owner
PO BOX 221 MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5138
Well No.
MICHAEL, JEFFREY H.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. ...*

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

ROGER MOORE and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26th day of August, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 224'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 224' to 503'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 503' to 1825'. Cleaned 7 7/8" hole through the Pittsburgh Coal seam from 1018' to 1025'. Removed 688' of 8 5/8" casing from 506' to 1194'. Left 300' of 8 5/8" casing in the hole from 1194' to 1494'.		16" Conductor 8 5/8"	0' 691'	20' 300'
Cemented hole from 1825' back to surface as follows: From 1825' to 1225' with 120 sacks of Expandable Cement. From 1225' to 918' with 145 sacks of Thixotropic Cement with green dye. From 918' back to the Surface with 423 sacks of Expandable Cement. Cement did circulate at the Surface. Left 20' of 16" conductor casing in the hole from Surface to 20'.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>(1018' - 1025')</u>	<u>77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

RECEIVED
Office of Oil and Gas
NOV 17 2014
WV Department of Environmental Protection

... and that the work of plugging and filling said well was completed on the 23rd day of September, 2014


And further deponents saith not.

Roger Moore
Roger Moore
Kevin Wright
Kevin Wright

Sworn to and subscribed before me this 3 day of November 2014

Kara Beth Fost
Notary Public

My commission expires: 11/14/23



Permit No. 47-049-02348-P
Well No. 5138

11/21/2014