

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

MILDRED H PRICHARD HEIRS (C/O PHIL PRICHARD)
Lease or Property Owner
PO BOX 108 MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

MANNINGTON 7.5'
Well Location

MANNINGTON
District

MARION
County

3934
Well No.

PRICHARD, MILDRED H HEIRS
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. ...*

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 30th day of October, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed 12 1/4" hole from the Surface to 214'. Reduced hole to 9 7/8". Cleansed 9 7/8" hole from 214' to 1084'. Reduced hole to 7 7/8". Cleansed 7 7/8" hole from 1084' to 1249'. Tagged solid plug at 1249'. Cleansed 9 7/8" hole through the Pittsburgh Coal seam from 812' to 819'. Left 28' of 10 3/4" casing in the hole from 214' to 242'. Left an unknown amount of 8 5/8" casing in the hole from 1168' to an unknown depth. Left 30' of 16" conductor casing in the hole from Surface to 30'.	<u>Cemented hole from 1249' back to surface as follows:</u> From 1249' to 1019' with 70 sacks of Expandable Cement. From 1019' to 712' with 155 sacks of Thixotropic Cement with green dye. From 712' back to the Surface with 335 sacks of Expandable Cement. Cement did circulate at the Surface.	16" Conductor	0'	30'
		10 3/4"	0'	28'
		8 5/8"	0'	Unknown
		RECEIVED Office of Oil and Gas JAN 19 2015 WV Department of Environmental Protection		
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	(812' - 819')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of November, 2014

And further deponents saith not.


Delbert Moore
Delbert Moore

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 22nd day of Dec 2014

Carole A Mayle
Notary Public

My commission expires: 9-12-17



Permit No. 47-049-02357-P
Well No. 3934

01/23/2015