

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL COMPANY  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
JEFFREY H. MICHAEL  
Lease or Property Owner  
PO BOX 221, MANNINGTON, WV 26582  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
GLOVER GAP 7.5'  
Well Location  
MANNINGTON  
District  
MARION  
County  
7701  
Well No.  
HAYS, J.L. & A.J.  
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Bill Hersholt* 3-24-15

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

RUSSELL SMALLWOOD and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16<sup>th</sup> day of December, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned 12 1/4" hole from Surface to 196'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 196' to 1212'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 742' to 748'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1212' to 1994'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1994' to 2064'. Tagged solid plug at 2064'. Left 16' of 16" conductor casing in the hole from Surface to 16'.  <u>Cemented hole from 2064' back to the Surface as follows:</u> From 2064' to 951' with 325 sacks of Expandable Cement. From 951' to 639' with 190 sacks of Thixotropic Cement with green dye. From 639' back to the Surface with 320 sacks of Expandable Cement. Cement did circulate at the surface.	16" Conductor	0'	16'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>(742' - 748')</u>	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED  
Office of Oil and Gas  
MAR 24 2015  
WV Department of  
Environmental Protection

... and that the work of plugging and filling said well was completed on the 7<sup>th</sup> day of January, 2015.

And further deponents saith not.

*Russell Smallwood*  
Russell Smallwood


*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 9 day of February 2015

*Kara Beth Forst*  
Notary Public

03/27/2015

My commission expires: 11/4/23



Permit No. 47-049-02370-P  
Well No. 7701