

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
ANNA M. MIKE (C/O ROBERT HAYES)  
Lease or Property Owner  
324 N. WASHINGTON ST, APT 1, MILLERSBURG, OH 44654  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
MANNINGTON 7.5'  
Well Location  
MANNINGTON  
District  
MARION  
County  
3932  
Well No.  
MIKE, ANNA M.  
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Bill Haddock* 12-15-15

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**MICHAEL MITCHELL** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13<sup>th</sup> day of October, 2015 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 310'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 310' to 1036'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1036' to 1139'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 1139' to 1142'. Tagged solid plug at 1142'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 737' to 744'. Left 10' of 16" conductor casing in the hole from Surface to 10'.  <b>Cemented hole from 1142' back to Surface as follows:</b> From 1142' to 944' with 90 sacks of Expandable Cement. From 944' to 628' with 185 sacks of Thixotropic Cement with dye. From 628' back to the Surface with 345 sacks of Expandable Cement. Cement did circulate at the Surface.	16" Conductor	0'	10'	
<b>Coal Seams</b>		<b>Description of Monument</b>		
Pittsburgh	(737' - 744')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED  
Office of Oil and Gas  
DEC 16 2015  
WV Department of  
Environmental Protection

... and that the work of plugging and filling said well was completed on the 23<sup>rd</sup> day of October, 2015


And further deponents saith not.

*Michael P. Mitchell*  
Michael Mitchell  
*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 9<sup>th</sup> day of Nov 2015

*Carol A. Mayle*  
Notary Public

My commission expires: 9-12-17



Permit No. 47-049-02404-P  
Well No. 3932