

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOL ENERGY
Lease or Property Owner
1000 CONSOL ENERGY DRIVE, CANONSBURG, PA 15317
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5100
Well No.
CONSOL ENERGY
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Bob Hoodasket 7-13-16*

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MICHAEL MITCHELL and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of June, 2016 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 292'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 292' to 1421'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1421' to 1515'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1515' to 1528'. Reduced hole to 3 1/2" stinger. Cleaned 3 1/2" hole from 1528' to 1533'. Tagged solid plug at 1533'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1108' to 1115'. Left 12' of 16" conductor casing in the hole from Surface to 12'. <u>Cemented hole from 1533' back to the Surface as follows:</u> From 1533' to 1315' with 75 sacks of Expandable Cement. From 1315' to 1005' with 200 sacks of Thixotropic Cement with dye. From 1005' back to the Surface with 495 sacks of Expandable Cement. Cement did circulate at the Surface.	16"	0'	12'	
Coal Seams	Description of Monument			
Pittsburgh	(1108' - 1115')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		


... and that the work of plugging and filling said well was completed on the 15th day of June, 2016.

And further deponents saith not.

Michael Mitchell
Michael Mitchell
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 5th day of July 2016

My commission expires: 9-12-17



Carol A. Mayle
Notary Public

Permit No. 47-049-02414-P
Well No. 5100