

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**CONSOLIDATION COAL CO.**  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
**CONSOLIDATION COAL CO.**  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
**DELBERT R. TRIPLETT**  
Lease or Property Owner  
26 JOES RUN RD MANNINGTON, WV 26582  
Address

**CONSOLIDATION COAL CO.**  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
GLOVER GAP 7.5'  
Well Location  
**MANNINGTON**  
District  
**MARION**  
County  
**5236**  
Well No.  
**N.C. HAWKINS**  
Farm

 COPY

STATE INSPECTOR SUPERVISING PLUGGING S. P. DeWitt

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**ROGER D. MOORE** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23rd day of June, 2017 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned hole with 12 1/4" bit from surface to 386'. Reduced hole to 9 7/8" bit. Cleaned hole with 9 7/8" bit from 386' to 1228'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam 846' to 854'. Pulled 7" casing from 1228' to 1396'. Left 7" casing in hole from 1396' to unknown depth. Cleaned hole with 9 7/8" bit from 1228' to 1396'. Reduced hole to 6 1/4". Cleaned hole with 6 1/4" bit from 1396' to 1924'.	7"  16"	168'  0'	Unknown  21'
<b>Cemented hole from 1924' back to Surface as follows:</b> From 1924' to 1054' with 240 sacks of Expandable cement. Cemented from 1054' to 746' with 165 sacks of Thixotropic cement. Cemented from 746' to 312' with 165 sacks of Expandable cement. Cemented from 312' to surface with 185 sacks of Expandable cement. A total of 165 sacks of Thixotropic and 590 sacks of Expandable cement were used to cement in the well. Cement did circulate at the surface. Left 20' of 16" conductor in hole from surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	(846' - 854')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 20<sup>th</sup> day of July, 2017

And further deponents saith not.


Roger D. Moore  
Roger D. Moore

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 5<sup>th</sup> day of Sept 2017

Carol A. Marshall  
Notary Public

My commission expires: 9-12-17



Permit No. 47-049-02455-P  
Well No. 5236  
Latitude: 39° 32' 0.925"N  
Longitude: 80° 25' 20.62"W

10/06/2017

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

 COPY

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: N.C. Hawkins Operator Well No.: 5236

LOCATION: Elevation: 1166.84' Quadrangle: Glover Gap 7.5'

District: Mannington County: Marion

Latitude: \_\_\_\_\_ Feet South of 39 Deg. 32 Min. 9.25 Sec.

Longitude: \_\_\_\_\_ Feet West of 80 Deg. 25 Min. 20.62 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co Coal Operator 1 Bridge St  
or Owner Monongah, WV 26554

Agent Ronnie Harsh Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date 05/16/2017

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Marion ss:


Roger D. Moore and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 23rd day of June, 2017, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable	1936'	1054'		
Thixotropic	1054'	746'		
Expandable	746'	Surface		
7"	1396'	Unknown	168'	Unknown
16" Conductor	Surface	21'	0'	21'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 20th day of July, 2017.

And further deponents saith not. Roger Moore  
Kevin S. Wright

Sworn and subscribe before me this 11<sup>th</sup> day of Sept, 20 17



My commission expires: 9-12-17 Cardlea A Mayle  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: S. J. O'Donnell Title: OOG Inspector