

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PARKER Operator Well No.: 71396

LOCATION: Elevation: 1056' Quadrangle: MANNINGTON 7.5'  
District: LINCOLN County: MARION  
Latitude: 6937' Feet South of 39 Deg. 35 Min. 00 Sec.  
Longitude: 10054' Feet West of 80 Deg. 15 Min. 00 Sec.

Well Type: OIL  GAS

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator OHIO VALLEY RESOURCES INC, ET AL  
601 57TH STREET or Owner 46226 NATIONAL ROAD  
CHARLESTON, WV 25304 ST CLAIRSVILLE, OH 43950

Agent H. JASON HARMON Coal Operator  
Permit Issued Date 04-30-2025 or Owner

RECEIVED  
Office of Oil and Gas

JUL 10 2025

WV Department of  
Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of LEWIS ss:


JAMES CLAYTON ("CLAY") COCHRAN and KEVIN PAUL QUESENBERY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 27TH day of JUNE, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	1927'		2" TBG (1927')	0
BH PLUG CEMENT	1927'	1627'	PUMP CLASS A CEMENT (60 SACKS)	GEL SPACER (1627' TO 1125')
PERF 8 HOLES	1077' & 300'	(4 SHOTS AT EACH INTERVAL)		
CEMENT PLUG	1125'	1025'	PUMP CLASS A CEMENT (20 SACKS)	GEL SPACER (1025' TO 350')
SURFACE CEMENT PLUG	350'	SURFACE	PUMP CLASS A CEMENT (143 SACKS)	

Description of monument: ONE JOINT PIPE: 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 1ST day of JULY, 2025.

And further deponents saith not.

*[Signature of Kevin P. Quesenberg]*



Sworn and subscribe before me this 9TH day of JULY, 2025

My commission expires: OCTOBER 10, 2029

*[Signature of P. Wayne Ammons]*

Notary Public

Affidavit reviewed by the Office of Oil and Gas:

*[Signature of Jeff A. Probst]*

Title:

INSPECTOR 7-10-2025  
07/11/2025



RECEIVED  
Office of Oil and Gas  
JUL 10 2025  
WV Department of  
Environmental Protection

07/11/2025