

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: POLE CAT HOLDGS Operator Well No.: 70025

LOCATION: Elevation: 1155' Quadrangle: MANNINGTON 7.5'
District: LINCOLN County: MARION
Latitude: 2940' Feet South of 39 Deg. 32 Min. 30 Sec.
Longitude: 5068' Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL GAS

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator _____
601 57TH STREET or Owner _____
CHARLESTON, WV 25304 _____
Agent H. JASON HARMON Coal Operator _____
Permit Issued Date 03-31-2025 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of LEWIS ss:

JOSEPH LARRY GREENLIEF and JOSHUA WAYNE DAVIS being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1ST day of JULY, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD		2200'	5/8" RODS (2150'); 2" TBG (2200')	0' 2" TUBING
BH PLUG (108 SKS CLASS A)	2200'	1918'		1640' 7" CASING
Perforated (4shots ea. interval)	1155', 600' & 427'			1075' 8-1/4" CASING
PLUG (36 SKS CLASS A)	1918'	1618'		234' 10" CASING
6% GEL SPACER	1618'	1205'		
PLUG (17 SKS CLASS A)	1205'	1105'		
6% GEL SPACER	1105'	650'		*** SEE ATTACHED PAGE 2 ***

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 11TH day of JULY, 2025.

And further deponents saith not. Joseph L Greenlief
Joshua Wayne Davis



Sworn and subscribe before me this 9TH day of MARCH, 2026

My commission expires: OCTOBER 10, 2029

P. Wayne Ammons
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Robert L. Hitt 4-2-26 Title: OG Inspector

04/03/2026

**STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS**

**AFFIDAVIT OF PLUGGING AND FILLING WELL
PAGE 2**

TYPE	FROM	TO	PIPE REMOVED	LEFT
PLUG (18 SKS CLASS A)	650'	550'		
6% GEL SPACER	550'	477'		
SURFACE PLUG (41 SKS CLASS A)	477'	SURFACE		



04/03/2026

API# 47-049-02541



☀ 197°S (T) ● 39.533600°N, 80.309524°W ±45ft ▲ 1206ft



04/03/2026