

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: FLUHARTY Operator Well No.: 71393

LOCATION: Elevation: 1183' Quadrangle: MANNINGTON 7.5'  
District: LINCOLN County: MARION  
Latitude: 6774' Feet South of 39 Deg. 35 Min. 00 Sec.  
Longitude: 8347' Feet West of 80 Deg. 15 Min. 00 Sec.

Well Type: OIL ☒ GAS ☒

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator OHIO VALLEY RESOURCES INC, ET AL  
601 57TH STREET or Owner 46226 NATIONAL ROAD  
CHARLESTON, WV 25304 ST CLAIRSVILLE, OH 43950  
Agent H. JASON HARMON Coal Operator \_\_\_\_\_  
Permit Issued Date 04-30-2025 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of LEWIS ss:

JAMES CLAYTON ("CLAY") COCHRAN and KEVIN PAUL QUESENBERRY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10TH day of JUNE, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	2033'			
BH PLUG CEMENT	2033'	1414'	PUMP CLASS A CEMENT (100 SACKS)	GEL SPACER (1414' TO 1150')
PERF 8 HOLES	1100' & 300'	(4 SHOTS AT EACH INTERVAL)		
CEMENT PLUG	1150'	1030'	PUMP CLASS A CEMENT (17 SACKS)	GEL SPACER (1030' TO 350')
SURFACE CEMENT PLUG	350'	SURFACE	PUMP CLASS A CEMENT (90 SACKS)	


Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 17TH day of JUNE, 2025.

And further deponents saith not.

Sworn and subscribe before me this 19TH day of JUNE, 2025

My commission expires: OCTOBER 10, 2029

Notary Public



Affidavit reviewed by the Office of Oil and Gas: Jeff A Propst Title: Inspector 6/25/2025

06/27/2025





06/27/2025