

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PARKER Operator Well No.: 71394

LOCATION: Elevation: 1205' Quadrangle: MANNINGTON 7.5'
District: LINCOLN County: MARION
Latitude: 6345' Feet South of 39 Deg. 35 Min. 00 Sec.
Longitude: 9626' Feet West of 80 Deg. 15 Min. 00 Sec.

Well Type: OIL ☒ GAS ☒

Company: UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator: OHIO VALLEY RESOURCES INC, ET AL
601 57TH STREET or Owner: 46226 NATIONAL ROAD
CHARLESTON, WV 25304 ST CLAIRSVILLE, OH 43950

Agent: H. JASON HARMON

Permit Issued Date: 04-30-2025

Coal Operator or Owner: RECEIVED
Office of Oil and Gas

JUL 10 2025

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of LEWIS ss:

WV Department of
Environmental Protection

JAMES CLAYTON ("CLAY") COCHRAN and KEVIN PAUL QUESENBERY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18TH day of JUNE, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	1923'		2" TBG (1923')	0
BH PLUG CEMENT	1880'	1450'	PUMP CLASS A CEMENT (100 SACKS)	GEL SPACER (1450' TO 1240')
PERF 8 HOLES	1226' & 300'	(4 SHOTS AT EACH INTERVAL)		
CEMENT PLUG	1240'	1090'	PUMP CLASS A CEMENT (31 SACKS)	GEL SPACER (1090' TO 300')
SURFACE CEMENT PLUG	300'	SURFACE	PUMP CLASS A CEMENT (169 SACKS)	

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10" BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 25TH day of JUNE, 2025.


And further deponents saith not.

Kevin P. Quesenberry

Sworn and subscribe before me this 9TH day of JULY, 2025

My commission expires: OCTOBER 10, 2029

P. Wayne Ammons
Notary Public



Affidavit reviewed by the Office of Oil and Gas:

Jeff A. Propst

Inspector 7-10-2025
Title: 07/11/2025

RECEIVED
Office of Oil and Gas

JUL 10 2025

WV Department of
Environmental Protection



07/11/2025