

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: EARL Operator Well No.: 71404

LOCATION: Elevation: 1132' Quadrangle: MANNINGTON 7.5'  
District: LINCOLN County: MARION  
Latitude: 9470' Feet South of 39 Deg. 35 Min. 00 Sec.  
Longitude: 31' Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL  GAS

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator OHIO VALLEY RESOURCES INC, ET AL  
601 57TH STREET or Owner 46226 NATIONAL ROAD  
CHARLESTON, WV 25304 ST CLAIRSVILLE, OH 43950  
Agent H. JASON HARMON Coal Operator \_\_\_\_\_  
Permit Issued Date 04-24-2025 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of LEWIS ss:

JOSEPH LARRY GREENLIEF and JOSHUA WAYNE DAVIS being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 31ST day of JULY, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD		1163'	NONE (NO TUBING IN WELL)	1254' 8-1/4" CASING
Perforated (4shots ea. interval)	1132', 725' & 300'		NOTE: THERE WAS ONLY OPEN	420' 10" CASING
BH PLUG (185 SKS CLASS A)	1163'	1063'	8-1/4" CASING PRE-PLUGGING.	
6% GEL SPACER	1063'	775'		
PLUG (39 SKS CLASS A)	775'	675'		
6% GEL SPACER	675'	350'		
SURFACE PLUG (138 SKS CLASS A)	350'	SURFACE		

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 29TH day of AUGUST, 2025.


And further deponents saith not.

*Joseph Greenleaf*  
*Joshua Wayne Davis*

Sworn and subscribe before me this 9TH day of MARCH, 2026

My commission expires: OCTOBER 10, 2029

*P. Wayne Ammons*  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Robert J. Hitt 3-18-26 Title: OG Inspector

04/03/2026



API# 47-049-02549



04/03/2026