

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: HOVATTER Operator Well No.: 71684

LOCATION: Elevation: 1374' Quadrangle: MANNINGTON 7.5'
District: MANNINGTON County: MARION
Latitude: 8855' Feet South of 39 Deg. 35 Min. 30 Sec.
Longitude: 2713' Feet West of 80 Deg. 20 Min. 00 Sec.

Well Type: OIL ☒ GAS ☒

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator CONSOLIDATION COAL COMPANY, C/O LEATHERWOOD, INC.
601 57TH STREET or Owner CNX CENTER
CHARLESTON, WV 25304 1000 CONSOL ENERGY DRIVE
Coal Operator CANONSBURG, PA 15317
Agent H. JASON HARMON or Owner
Permit Issued Date 04-09-2025

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of LEWIS ss:

JAMES CLAYTON ("CLAY") COCHRAN and KEVIN PAUL QUESENBERY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 30TH day of MAY, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	2289'		5/8" RODS (2250'); 2-3/8" TBG (2289')	NONE (5/8" RODS; 2-3/8" TBG)
BH PLUG CEMENT	2280'	1980'	PUMP CLASS A CEMENT (79 SACKS)	
CEMENT PLUG	1970'	1730'	PUMP CLASS A CEMENT	GEL SPACER (1730' TO 1400')
PERF 6 HOLES	1346' & 300'	(3 SHOTS AT EACH INTERVAL)		
CEMENT PLUG	1400'	1300'	PUMP CLASS A CEMENT (111 SACKS)	GEL SPACER (1300' TO 350')
SURFACE CEMENT PLUG	350'	SURFACE	PUMP CLASS A CEMENT (139 SACKS)	


Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 12TH day of JUNE, 2025.

And further deponents saith not.

Sworn and subscribe before me this 19TH day of JUNE, 2025

My commission expires: OCTOBER 10, 2029

Notary Public



Affidavit reviewed by the Office of Oil and Gas: Jeff A Probst

Title: Inspector 6/19/2025

06/27/2025



06/27/2025