

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: DANIELS Operator Well No.: 71685

LOCATION: Elevation: 1237' Quadrangle: MANNINGTON 7.5'
District: MANNINGTON County: MARION
Latitude: 8338' Feet South of 38 Deg. 32 Min. 30 Sec.
Longitude: 2524' Feet West of 80 Deg. 20 Min. 00 Sec.

Well Type: OIL GAS

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator CONSOLIDATION COAL COMPANY, C/O LEATHERWOOD, INC.
601 57TH STREET or Owner CNX CENTER
CHARLESTON, WV 25304 1000 CONSOL ENERGY DRIVE
Coal Operator CANONSBURG, PA 15317
Agent H. JASON HARMON or Owner _____
Permit Issued Date 03-31-2025

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of LEWIS ss:

JAMES CLAYTON ("CLAY") COCHRAN and KEVIN PAUL QUESENBERY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8TH day of APRIL, 2025, and the well was plugged and filled in the following manner:

RECEIVED
Office of Oil and Gas

MAY 01 2025

WV Department of
Environmental Protection

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	2152'			
PULL TBG	2152'	SURFACE	2" TBG (2152')	0'
COULD NOT PULL CSG	SURFACE	1700'	7" CSG (NONE)	1700'
BH PLUG CEMENT	2152'	1625'	PUMP CLASS A CEMENT (112 SACKS)	
GEL SPACER	1625'	1287'		
PERF 12 HOLES	1230'	110'	PUMP CLASS A CEMENT (82 SACKS) - 1287' TO 1087'	GEL SPACER 1087' TO 400'
SURFACE PLUG CEMENT	400'	SURFACE	PUMP CLASS A CEMENT (146 SACKS)	

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 17TH day of APRIL, 2025.


And further deponents saith not.

[Handwritten signature of Kevin Paul Quesenberry]

Sworn and subscribe before me this 29TH day of APRIL, 2025

My commission expires: OCTOBER 10, 2029

[Handwritten signature of P. Wayne Ammons]
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Cyff Puxert Title: DOG Inspector

05/02/2025



RECEIVED
Office of Oil and Gas

MAY 01 2025

WV Department of
Environmental Protection

RECEIVED
Office of Oil and Gas

MAY 01 2025

05/02/2025
WV Department of
Environmental Protection