

572A

Lincoln District, Marion County, W. Va.

By Russell Purbee, Beach Ave., Fairmont, W. Va.

Abandoned under permit No.-11

On 125 $\frac{1}{2}$ acres.

Elevation, 1232.22' (ground: 1235.72' (D. P.))

Surface owned by Annie Price, Rachel, W. Va., and coal by Jamison
Coal & Coke Co., Farmington, W. Va.

Drilling completed Aug. 16, 1914.

No record of water.

10" casing, 722'; 6 $\frac{1}{2}$ " 1956'; 5 $\frac{1}{2}$ " 2630'; 4 $\frac{1}{2}$ " liner, 282'; all left in.
Coal was encountered at 675-683'.

Oil well. Record to Dept. of Mines stamped Oct. 14, 1918.

Record to RRT from Mrs. Griffith Jan. 22, 1919. Old File No. 641.

	Top.	Bottom.
Pittsburgh Coal	675	- 683
Little Buckard Sand	1040	- 1070
Big Buckard Sand	1180	- 1210
Cap Sand	1395	- 1530
1st Salt Sand	1605	- 1655
2nd Salt Sand	1695	- 1716
Little Linc	1906	- 1921
Permal Cove	1921	- 1926
Big Linc	1926	- 1991
Big Injen Sand (oil and gas, 2100')	1991	- 2176
Squaw Sand	2145	- 2170
Fifty-foot Sand	2385	- 2630
Thirty-foot Sand	2720	- 2750
Gordon Gray Sand	2887	- 2906
Gordon Sand (oil, 2915')	2906	-
Total depth		2925



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

641

WELL RECORD

Permit No. 572-A


Oil or Gas Well _____ (KIND)

Company Russell Furbee
 Address Benoni Ave, Fairmont, W.Va.
 Farm A. O. Talkington Acres 125 3/4
 Location (waters) _____
 Well No. 14 Elev. 1235.72
 District Lincoln County Marion
 The surface of tract is owned in fee by Archie Price
 Address Rachel
 Mineral rights are owned by Coal - Jamison Coal & Coke Co.
 Address Farmington, W.Va.
 Drilling commenced No Record
 Drilling completed Aug. 16, 1914
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water No Record feet _____ feet
 Salt water No Record feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
13			
10	722	722	Size of
8 1/4			
6 3/8	1956	1956	Depth set
5 3/16	2630	2630	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
4" x 4 1/2" 282			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT 675 FEET 96 INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			675	683			
L. Dunkard			1040	1070			
Big Dunkard			1140	1210			
Gas Sand			1395	1530			
1st Salt			1605	1655			
2nd Salt			1695	1716			
L. Lime			1906	1921			
Pencil Cave			1921	1926			
Big Lime			1926	1991			
Big Injun			1991	2136			
Squaw Sand			2145	2170			
Fifty Foot.			2585	2638	Oil & Gas	2100	
Thirty Foot			2720	2750			
Gordon Stray			2887	2906			
Gordon Sand			2906		Oil	2915	
Total Depth				2925			



(Over)

JAN 22 1949