




LATITUDE 39 30

LONGITUDE 80 20



7'5 OGIS topo location

7.5' loc \_\_\_\_\_ 15' loc \_\_\_\_\_  
 \_\_\_\_\_ (calc.) \_\_\_\_\_

Company \_\_\_\_\_ 1884 \_\_\_\_\_

Farm M M MARTIN

Quad SHINNSTON

County MARION

District LINCOLN

WELL LOCATION MAP

File No. 30700

700A

Lincoln District, Marion County, W. Va.  
 By Pittsburgh & W. Va. Gas Co., Clarksburg, W. Va.  
 Abandoned under permit Mar-.....-17  
 On 3<sup>1</sup>/<sub>2</sub> acres; Clarksburg N/W 1-2.  
 Elevation, 1141' Y. A.  
 Surface owned by Herbert Martin, R. D. No. 4, Mannington, W. Va., and  
 minerals by N. M. and Pearl G. Martin, R. D. No. 4, Mannington, W. Va.  
 Drilling commenced April 25, 1906; completed May 31, 1906.  
 10" casing, 285' (pulled); 8<sup>1</sup>/<sub>2</sub>" 946' (pulled); 6<sup>1</sup>/<sub>2</sub>" 1721'.  
 Coal was encountered at 275-280, 397-405, and 975-980'.  
 Water, 130, 1060, and 1350'.  
 Gas at 1876, 2305, 2619, and 2775'.  
 Gas well. Record to Dept. of Mines dated June 20, 1949; stamped  
 Mar. 17, 1951.  
 Record to ROT from Mrs. Griffith Dec. 10, 1952. O.P.No.858.

	Top.	Bottom.
Line, white, hard	0	65
Slate, black, soft	65	115
Line, white, hard	115	165
Slate, white, soft	165	175
Line, white, hard	175	275
Mapletown (Sewickley) Coal, soft	275	280
Slate, white, soft	280	300
Line, white, hard	300	365
Slate, white, soft	365	375
Line, white, hard	375	397
Pittsburgh Coal, soft	397	405
Line, white, hard	405	500
Slate, white, soft	500	550
Red rock, soft	550	650
Line, white, hard	650	700
Red rock, soft	700	705
Line, white, hard	705	730
Red rock, soft	730	750
Little Dunkard Sand, hard	750	770
Red rock, soft	770	800
Slate, black, soft	800	850
Sand, white, hard	850	855
Red rock, soft	855	900
slate, black, soft	900	950
Sand, white, hard	950	965
Slate, black, soft	965	975
Coal, soft	975	980
sand, white, hard	980	990
slate, black, soft	990	1050
Gas Sand, white, soft	1050	1275
slate, black, soft	1275	1280
Salt Sand, white, hard	1280	1450
Red rock, soft	1450	1550
Line, white, hard	1550	1570
Sand, white, hard	1570	1600
Red rock, soft	1600	1650
Little Line, white, hard	1650	1697
Pencil Cave, black, soft	1697	1702
Big Line, white, hard	1702	1763
Big Injun Sand, white, hard	1763	1903
lime shells, hard	1903	2180

K. M. MARTIN NO. 1884 WELL (Contd.)

	Top.	Bottom.
Sand, white, hard	2180	- 2200
Lime, white, hard	2200	- 2220
Sand, white, hard	2220	- 2250
Slate, black, soft	2250	- 2300
50-Ft. Sand, white, hard	2300	- 2385
Slate, black, soft	2385	- 2400
Sand, white, hard	2400	- 2420
Slate and shells, hard	2420	- 2460
30-Ft. Sand, white, hard	2460	- 2485
Shells and red rock, soft	2485	- 2525
Lime, white, hard	2525	- 2550
Stray Sand, white, hard	2550	- 2600
Gordon Sand, white, hard	2600	- 2640
4th Sand, white, hard	2640	- 2660
Slate, black, soft	2660	- 2770
5th Sand, white, soft	2770	- 2785
Unrecorded	2785	- 2807
Total depth		2907



858

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

WELL RECORD

Permit No. MAR-700 A

Oil or Gas Well "GAS"  
(KIND)


Company Pittsburgh & West Va Gas Company.  
 Address Clarksburg, West Va.  
 Farm M. H. Martin Acres 3-3/4  
 Location (waters) Clks. N/E. 1-C  
 Well No. 1984 Elev. 1141' VA  
 District Lincoln County Marion  
 The surface of tract is owned in fee by Herbert Martin  
R.D.#4 Address Mannington, W. Va.  
 Mineral rights are owned by M. H. & Pearl G. Martin  
R.D.#4 Address Mannington, W. Va.  
 Drilling commenced April 25, 1906  
 Drilling completed May 31, 1906  
 Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
 With \_\_\_\_\_

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	<u>285'</u>	<u>None</u>	Size of
8 1/4	<u>946'</u>	<u>None</u>	
6 5/8	<u>1721'</u>	<u>1721'</u>	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
 \_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

CASING CEMENTED	SIZE	No. Ft.	Date
COAL WAS ENCOUNTERED AT <u>275</u> FEET <u>60</u> INCHES			
	<u>975</u>	<u>96</u>	<u>60</u>
	<u>397</u>		

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Lime	White	Hard	0	65			
Slate	Black	Soft	65	115			
Lime	White	Hard	115	165	Water	130'	
Slate	"	Soft	165	175			
Lime	"	Hard	175	275			
M.F. Coal		Soft	275	280			
Slate	White	Soft	280	300			
Lime	"	Hard	300	365			
Slate	"	Soft	365	375			
Lime	"	Hard	375	397			
Pgh. Coal		Soft	397	405			
Lime	White	Hard	405	500			
Slate	"	Soft	500	550			
Red Rock	Red	Soft	550	650			
Lime	White	Hard	650	700			
Red Rock	Red	Soft	700	705			
Lime	White	Hard	705	730			
Red Rock	Red	Soft	730	750			
Little Dunkard		Hard	730	770			
Red Rock	Red	Soft	770	800			
Slate	Black	Soft	800	850			
Sand	White	Hard	850	855			
Red Rock	Red	Soft	855	900			
Slate	Black	Soft	900	950			
Sand	White	Hard	950	965			
Slate	Black	Soft	965	975			
5012X Coal		"	975	980			
Sand	White	Hard	980	990			
Slate	Black	Soft	990	1050			
Gas Sand	White	"	1050	1275	Water	1060'	
Slate	Black	Soft	1275	1280			
Salt Sand	White	Hard	1280	1450	Water	1350'	
Red Rock	Red	Soft	1450	1550			
Lime	White	Hard	1550	1570			
Sand	"	Hard	1570	1600			
Red Rock	Red	Soft	1600	1650			
Little Lime	White	Hard	1650	1697			
Pencil Cove	Black	Soft	1697	1702			



DEC 10 1952

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Big Lime	White	Hard	1702	1763			
Big Injun	"	"	1763	1903	Gas	1876'	
Lime Shells		"	1903	2180			
Sand	White	"	2180	2200			
Lime	"	"	2200	2220			
Sand	"	"	2220	2250			
Slate	Black	Soft	2250	2300			
30 Ft. Sand	White	Hard	2300	2385	Gas	2305'	
Slate	Black	Soft	2385	2400			
Sand	White	Hard	2400	2420			
Slate Shells		"	2420	2460			
30 Ft. Sand	White	"	2460	2485			
Shells & Red Rock		Soft	2485	2525			
Lime	White	Hard	2525	2550			
Stray Sand	"	"	2550	2600			
Gordon Sand	"	"	2600	2610	Gas	2619'	
<del>Un-recorded</del>			<del>2610</del>	<del>2660</del>			
4th. Sand	"	"	2610	2660			
Slate	Black	Soft	2660	2770			
5th. Sand	White	"	2770	2785	Gas	2775'	
Un-recorded			2785	2807			
Total depth.....				2837			

June 20, 1949

Date \_\_\_\_\_, 19\_\_\_\_

FITTSBURGH & WEST VA GAS COMPANY

APPROVED \_\_\_\_\_, Own

By W. M. West

(Title)



