


Company Hope Natural Gas Co
 Address Clarksburg, W. Va.
 Farm Frank Straight
 Tract Acres 65 Lease No. 61859

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

LATITUDE 39 35



LONGITUDE 80 10 00

7'5 OGIS topo location

7.5' loc _____ 15' loc _____
 _____ (calc.) _____

Company _____ 9558 ^{MP} (260)

Farm FRANK STRAIGHT

Quad GRANT TOWN

County MARION

District PAW PAW

WELL LOCATION MAP

File No. 30705

FRANK STRAIGHT NO. 958 (M.P.260) WELL.

7054

Fewpaw District, Marion County, W. Va.

By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.

Abandoned under permit Mar-.....-A7

On 65 acres,

Elevation, 1150' L.

Drilling completed about 1915.

No water recorded.

10" casing, 460' (pulled); 8" casing, 1512' (630' left in); 6" casing, 1710';

5" casing, 1950'; 3" tubing, 1960'; 4" liner, 348'. Casing not cemented.

Coal was encountered at 15-20 and 455-462'.

Gas well. Record to Dept. of Mines dated March 12, 1951.

Record to ROT from Mrs. Griffith June 28, 1951. Old File No. 797.

	Top.	Bottom.
Coal	15	20
Pittsburgh Coal	455	462
Big Dark Sand	1012	1033
First Salt Sand	1275	1315
Second Salt Sand	1360	1475
Little Lime	1671	1683
Pencil Cave	1683	1700
Big Lime	1700	1764
Big Injun Sand (gas, 1853, 1874')	1764	1896
Fifty-foot Sand (gas,.....?)	2310	2350 (Est.)
Total depth		3015
Present depth about		2400



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

797

WELL RECORD

Permit No. MAR-705-A

Oil or Gas Well X (KIND)


Company Hope Natural Gas Company.
 Address 445 West Main St. Clarksburg, W. Va.
 Farm Frank Straight Acres 65
 Location (waters) _____
 Well No. 9558 M.P. 260 Elev. 1150
 District Paw Paw County Marion
 The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____
 Drilling commenced _____
 Drilling completed about 1915
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water none recorded feet _____ feet
 Salt water none recorded feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
18			
10	<u>460</u>	<u>Pulled</u>	Size of
8 1/4	<u>1512</u>	<u>630</u>	
6 5/8	<u>1710</u>	<u>1710</u>	Depth set
5 3/16	<u>1950</u>	<u>1950</u>	
3	<u>1960</u>	<u>1960</u>	Perf. top
2			Perf. bottom
Liners Used <u>4"</u>	<u>348</u>	<u>348</u>	Perf. top
			Perf. bottom

CASING CEMENTED NOT SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 15 FEET 60 INCHES
455 FEET 84 INCHES FEET INCHES
 FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Coal			<u>15</u>	<u>20</u>			
Pittsburgh Coal			<u>455</u>	<u>462</u>			
Big Dunkard			<u>1012</u>	<u>1033</u>			
First Salt			<u>1275</u>	<u>1315</u>			
Second Salt			<u>1360</u>	<u>1475</u>			
Little Lime			<u>1671</u>	<u>1683</u>			
Pencil cave			<u>1683</u>	<u>1700</u>			
Big Lime			<u>1700</u>	<u>1764</u>			
Big Injun			<u>1764</u>	<u>1896</u>	<u>gas</u>	<u>1858</u>	<u>1874</u>
Fifty foot			<u>2310</u>	<u>2350 EST</u>	<u>gas</u>	<u>?</u>	
Drilled to				<u>3015</u>			
Present depth about				<u>2400</u>			



JUN 28 1951

