



New Location
 Drill Deeper
 Abandonment X

Coal - Eastern Gas & Fuel
 associates, Grant Town, W Va.
 Surface - Chas Toothman
 Potomac Ave, Fairmont W Va


Company Truman Smith
 Address Hundred W Va
 Farm Mary A Moore
 Tract / Acres 121 Lease No.

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP

LATITUDE 39 37 30

LONGITUDE 80 15



1.96S
1.09W

7'5 OGIS topo location

7.5' loc _____ 15' loc _____
 _____ (calc.) _____

Company _____

Farm MARY A. MOORE 1

Quad Grant Town

County Marion

District Yon Dow

WELL LOCATION MAP

File No. 30757

MARY A. MOORE NO. 1 WELL.

Pawpaw District, Marion County, W. Va.

By Truman Smith, Hundred, W. Va.

Abandoned under permit Mar-1-1943

On 121 acres,

Elevation, 1222' L.

Surface owned by Chas. Toothman, Potomac Ave., Fairmont, W. Va., and minerals by Eastern Gas & Fuel Assoc., Grant Town, W. Va.

Drilling commenced June 18, 1924; completed Sept. 12, 1924.

10" casing, 564'; 8" , 1242'; 6" , 1820'; all left in.

Gas well. Record to Dept. of Mines stamped Nov. 2, 1951.

Record to RCT from Mrs. Griffith July 9, 1952. C. F. No. 843.

	Top.	Bottom.
Mapletown (Sewickley) Coal	465	472
Pittsburgh Coal	547	554
Little Punkard Sand	910	925
Gas Sand	1299	1328
Salt Sand	1360	1392
Second Salt Sand	1520	1570
Little Lime	1790	1800
Pencil Cove	1800	1805
Big Lime	1805	1883
Big Injun Sand	1883	2000
50-Ft. Sand	2422	2438
30-Ft. Sand	2475	2495
5th Sand (gas at 2952')	2948	2964
Total depth		2994



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

843

WELL RECORD

Permit No. MAK-757-A


Oil or Gas Well X (KIND)

Company Truman Smith
 Address Hundred, W. Va.
 Farm Mary A. Moore Acres 121
 Location (waters) _____
 Well No. 1 Elev. 1222
 District Paw Paw County Marion
 The surface of tract is owned in fee by Chas. Seetham
Potomac Avenue Address Fairmont, W. Va.
 Mineral rights are owned by Eastern Gas & Fuel Ass.
 Address Grant Twon, W. Va.
 Drilling commenced June 18th, 1924
 Drilling completed Sept 12th, 1924
 Date Shot From _____ To _____
 With _____
 Open Flow /10ths Water in _____ Inch
 /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	564	564	Size of
8%	1242	1022	
6%	1820	1820	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Mapletown Coal			465	472			
Pittsburgh Coal			547	554			
Little Dunkard			910	925			
Gas Sand			1299	1328			
Salt Sand			1360	1392			
Second Salt Sand			1520	1570			
Little Lime			1790	1800			
Pencil Cave			1800	1805			
Big Lime			1805	1863			
Injun Sand			1863	2000			
50ft. Sand			2422	2438			
30ft. Sand			2475	2495	Gas at		
5th, Sand			2948	2964	2952		
Total Depth			2994				



#2 is Marion 43 (was 176A)