

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.R. & Alice Chambers Operator Well No.: M-1567

LOCATION: Elevation: 1215.08' Quadrangle: Cameron WV, PA
District: Cameron County: Marshall
Latitude: _____ Feet South of 39 Deg. 83 Min. 38.99 Sec.
Longitude: _____ Feet West of 80 Deg. 52 Min. 06.74 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent Jay Hores Coal Operator _____
Permit Issued Date 10/6/2022 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:

Matthew A. Yearsley and Chance Caldwell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of August, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expanding Cement with Gas Blocker	2900'	2292'	4 1/2" 1830'	1131'
Expanding Cement with Gas Blocker	2292'	1853'	6 5/8" 1070'	876'
Expanding Cement with Gas Blocker	1853'	1168'	8 1/4" 0'	1109'
Thixotropic Cement and Green Dye	1168'	687'	13" 0'	16'
Expanding Cement	687'	Surface		


Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 26th day of August, 2024.

And further deponents saith not. Matthew A. Yearsley
Chance Caldwell

Sworn and subscribe before me this 24th day of September, 2024

My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Strader Gower Title: 10/01/2024

10/18/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ALLEN L. WENDT
Lease or Property Owner
274 MCCRACKEN RD. CAMERON, WV 26033
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON, WV
Well Location
CAMERON
District
MARSHALL
County
M-1567
Well No.
B.R. & ALICE CHAMBERS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower *Strader Gower*
AFFIDAVIT 10/01/2024

STATE OF WEST VIRGINIA,
County of Marshall ss:
MATTHEW A. YEARSLEY and CHANCE CALDWELL being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of August, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In	
4 1/2" casing previously perforated at 2916' and 2727'. Perforated 4 1/2" casing with 6 shots each at 2600', 2400', 2200' and 2000'. Cemented hole from 2900' to 2292' with 55 sacks of Expandable Cement with Gas Blocker. Tagged Cement at 2292'. Cemented hole from 2292' to 1853' with 30 sacks of Expandable Cement with Gas Blocker. Removed 1830' of 4 1/2" casing from surface to 1830'. Left 1131' of 4 1/2" casing from 1830' to 2961'. Perforated 6 5/8" casing with 6 shots each at 1800', 1600', 1400' and 1200'. Removed 1070' of 6 5/8" casing from surface to 1070'. Left 876' of 6 5/8" casing from 1070' to 1946'. Tagged Cement at 1853'. Cemented from 1853' to 1168' with 115 sacks of Expandable Cement with Gas Blocker. Perforated 8 1/4" casing with 6 shots each at 994', 944', 894', 844', 804', 782', 777', 737' and 687'. Cut 8 1/4" casing at 799', 794', 791', 787' and 782'. Attempted to remove 8 1/4" casing by pulling 150% of string weight. All attempts were unsuccessful. The Pittsburgh Coal Seam is located at 787' to 794'		4 1/2"	1830'	1131'	
			6 5/8"	1070'	876'
			8 1/4"	0'	1109'
			13"	0'	16'
Cemented the hole from 1168' to surface as follows:					
Tagged Cement at 1168'. Cemented from 1168' to 687' with 170 sacks of Thixotropic Cement and a Green Dye additive. Tagged Cement at 687'. Cemented from 687' to surface with 175 sacks of Expandable Cement. Cement did circulate at the surface. A total of 545 sacks of was used to cement from 2900' to surface.					
Coal Seams		Description of Monument			
<u>Pittsburgh</u>	<u>787' to 794'</u>	<u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>			

... and that the work of plugging and filling said well was completed on the 26th day of August, 2024

And further deponents saith not.


Matthew A. Yearsley
Matthew A. Yearsley

Chance Caldwell
Chance Caldwell

Sworn to and subscribed before me this 24th, September 2024 *[Signature]*
Notary Public

My commission expires:

June 8th, 2027



Permit No. 47-051-00010
Well No. M-1567
Latitude: 39° 83' 38.99" N
Longitude: -80° 52' 06.74" W

10/18/2024