

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Eagle Natrium, LLC Operator Well No.: No. 5 Brine Well

LOCATION: Elevation: 685 ft. Quadrangle: New Martinsville, WV
District: Franklin County: Marshall
Latitude: 0 Feet South of 39 Deg. 44 Min. 45 Sec.
Longitude: 0 Feet West of 80 Deg. 50 Min. 48 Sec.

Well Type: OIL _____ GAS Brine X

Company Eagle Natrium, LLC/Axiall Corp. Coal Operator N/A
P.O. Box 191 or Owner _____
New Martinsville, WV 26155 _____
Agent J. Thomas Horan Coal Operator N/A
or Owner _____
Permit Issued Date 11/04/13

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:


[Signature] and Stephen Clark being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of May, 2014, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
1.) 5-1/2" x 17 lb. J 55 Casing	0	6190 ft.	6190 ft. to surface	33 ft.
2.) Set 8-5/8" Bridge Plug	6190 ft.	6190 ft.		
3.) Perforate 8-5/8" Casing	6070 ft.	6090 ft.		
4.) Cement 8-5/8" Casing	6190 ft.	5700 ft.		
5.) Gel 8-5/8" Casing	5700 ft.	1500 ft.	Continued below:	
6.) Perforate 8-5/8" Casing	1390 ft.	1410 ft.	8.) Gel 8-5/8" Casing from 1200 ft. to 300 ft.	
7.) Cement 8-5/8" Casing	1500 ft.	1200 ft.	9.) Cement 8-5/8" Casing from 300 ft. to Surface	

Received
JUL 21 2014
Office of Oil and Gas
Dept. of Environmental Protection

Description of monument: Metal plaque with well and API number and completion date and that the work of plugging and filling said well was completed on the 1st day of July, 2014.

And further deponents saith not. _____



Sworn and subscribe before me this 11 day of July, 2014

My commission expires: April 10, 2016

Karen Sapp
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: 7/18/2014 08/15/2014