

STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO. - OHIO VALLEY OPERATIONS
Coal Operator or Owner
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Address

CONSOLIDATION COAL CO. - OHIO VALLEY OPERATIONS
Name of Well Operator
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Complete Address

CONSOLIDATION COAL CO. - OHIO VALLEY OPERATIONS
Coal Operator or Owner
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Address
BRIAN K. MILLIKEN
Lease or Property Owner
3732 WICKHAM CIRCLE NW, UNIONTOWN, OH 44685
Address

MAJORSVILLE, WV 7.5'
Well Location
WEBSTER
District
MARSHALL
County
SGW-107
Well No.
ELDER, MAY
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Jason A. Wilkins
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of **MONONGALIA** ss:

MARK WILSON and **KEVIN WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 31st day of October, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing / Tubing Size	Casing Pulled	Casing Left In
Cleaned 3 3/8" hole through 4 1/2" casing from Surface to 1945'. Cut 4 1/2" casing at the following depths: 1750', 1648', 1550', 1450', and 1350'. Perforated 4 1/2" casing with 6 shots at the following depths: 1699', 1599', 1505', 1399', 1297', 1197', and 1097'. Cemented bottom hole plug from 1945' to 939' with 70 sacks of Expandable Cement. Jet cut 4 1/2", 7" and 8 5/8" and 10 3/4" casing at the following depths: 940', 890' and 840'. Removed 840' of 4 1/2" casing from Surface to 840'. Removed 840' of 7" casing from Surface to 840'. Removed 840' of 8 5/8" casing from Surface to 840'. Left 753' of 10 3/4" casing in the hole from 14' to 767'. Remaining 10 3/4" casing was bonded and was cut at the following depths: 742', 740', 738', 736', 734', 732', 683', and 633'. Left 10 3/4" casing through the Pittsburgh Coal seam from 732' to 739'. Left 1016' of 4 1/2" casing in the hole from 840' to 1586'. Left 960' of 7" casing in the hole from 840' to 1800'. Left 445' of 8 5/8" casing in the hole from 840' to 1285'. Left 16' of 16" conductor casing in the hole from Surface to 16'.		16" Conductor	0'	16'
		10 3/4" Casing	0'	753'
		8 5/8" Casing	840'	445'
		7" Casing	840'	960'
		4 1/2"	840'	1016'
<p>RECEIVED Office of Oil and Gas JAN 26 2015 WV Department of Environmental Protection</p>				
Cemented hole from top of bottom hole plug at 939' back to the Surface as follows:				
From 939' to 632' with 130 sacks of Thixotropic Cement with green dye. From 632' back to the Surface with 225 sacks of Expandable Cement. Cement did circulate at the surface.				
Coal Seams		Description of Monument		
Pittsburgh Coal	732' to 739'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing .Well marker attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 20th day of November, 2014

And further deponents saith not.

Mark Wilson
Mark Wilson


Kevin Wright
Kevin Wright

Sworn to and subscribed before me this 22 day of January 2015

01/30/2015

Kara Beth Forst
Notary Public

My commission expires: 11/4/23



Permit No. 47-051-00193-P
Well No. SGW-107