

FORM WR-38
(Affidavit of Plugging)

STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO., RIVER OPERATIONS
Coal Operator or Owner
RD. 4 BOX 425 MOUNDSVILLE, WV 26041
Address

CONSOLIDATION COAL CO., RIVER OPERATIONS
Name of Well Operator
RD. 4 BOX 425 MOUNDSVILLE, WV 26041
Complete Address

CONSOLIDATION COAL CO., RIVER OPERATIONS
Coal Operator or Owner
RD. 4 BOX 425 MOUNDSVILLE, WV 26041
Address

MAJORSVILLE, WV 7.5
Well Location

TIMOTHY D. & CATHY R. WARD
Lease or Property Owner
RR 1 BOX 47 DALLAS, WV 26036
Address

SANDHILL
District
MARSHALL
County
SGW-45
Well No.

WARD, TIMOTHY D. & CATHY R.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Russell Smallwood* 4-4-11

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

RUSSELL SMALLWOOD and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23rd day of December, 2010 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Plugs Used	Casing Pulled	Casing Left In
Formation		Size & Kind		
Cleaned 3 1/2" hole from surface to 1430'. Tagged plug at 1430'. Removed 4 1/2" casing from the surface to 850'. Left 580' 4 1/2" casing in the hole from 850' to 1430' do to extreme cement bond. Cut remaining 4 1/2" casing at 1228' and 1038'. Cement bottom hole from 1430' back to 850' with 50 sacks of Thixotropic Cement with green dye. Removed 8 5/8" casing from surface to 849'. Left 486' of 8 5/8" casing in the hole from 849' to 1335'. Removed all the 10 1/4" casing from the surface to 705'. Cleaned 12 1/4" hole from the surface to 850'. Tagged plug at 850'. Cleaned 12 1/4" hole thru Pittsburgh Coal 665' to 671'. Left 20' of 16" conductor pipe in hole from 20' to surface.	16" Conductor 10 1/4" Casing 8 5/8" Casing 4 1/2" Casing	0' 705' 849' 850'	20' 0' 486' 486'	
<u>Cement hole from 1430' to surface as follows:</u> From 1430' to 850' with 50 sacks of Thixotropic Cement with dye. From 850' to 571' with 195 sacks of Thixotropic Cement with dye. From 571' to surface with 355 sacks of Expandable Cement. A total of 600 sacks of cement were used to cement the hole from 1430' to the surface. Cement did circulate at surface.				
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>PITTSBURGH</u>	665' to 671'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well maker will be attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 14th day of January 2011

RECEIVED
Office of Oil & Gas

FEB 20 2013

Other deponents saith not.


Sworn to and subscribed before me this 28th day of March, 2011

Russell Smallwood
Russell Smallwood

Kevin S. Wright
Kevin S. Wright

Jacqueline L. Shriver
Notary Public

My Commission expires: March 15, 2020



Permit No. 47-051-00194-P
Well No. SGW-45

WV Department of
Environmental Protection

02/22/2013