

COAL OWNED BY Monongalia Improvement Co.

STORAGE...

NEW LOCATION...

DRILL DEEPER...

ABANDONMENT...

COMPANY The Manufacturers Light & Heat Co.

ADDRESS 800 Union Trust Bldg. Pittsburgh Pa.

FARM Arthur D. Fisher

TRACT _____ ACRES 244.7 LEASE NO. 21237

WELL (FARM) NO. 1 SERIAL NO. A124

ELEVATION (SPIRIT LEVEL) 1241

QUADRANGLE Cameron

COUNTY Marshall DISTRICT Sandhill

ENGINEER A.C. Streater E.L. _____

ENGINEER'S REGISTRATION NO. _____

FILE NO. _____ DRAWING NO. Y-13-626

DATE 127.16.1952 SCALE 1" = 800'

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP

FILE NO. MARS-230

+ DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS. SCALE 1 TO 62,500. LATITUDE AND LONGITUDE LINES BEING REPRESENTED BY BORDER LINES AS SHOWN.

- DENOTES ONE INCH SPACES ON BORDER LINE OF ORIGINAL TRACING.

9.056 0.022

WEST VIRGINIA DEPARTMENT OF MINES
OIL & GAS DIVISION
W E L L R E C O R D

Permit No. MARS 230
Cameron Quad.

Gas

Company Manufacturers Light & Heat Company
Farm Arthur D. Fisher Acres 116
Well No. 4124
District Marshall County -- Marshall
Commenced 1/18/52
Completed 2/19/52
Contractor M.C. Brumage & Sons, Waynesburg, Pa.
Volume 638,987
R.P. 450# 24 hours

CASING & TUBING


Cond.	16	16	
	10	748	748
	6 1/4	1358	1358
	4		1468

Anchor Packer 8 1/2 x 4"

Slate	0	28
Lime Shells	28	80
Lime	80	107
Sand	107	125
Lime Shells	125	140
Slate	140	200
Lime & Slate	200	225
Lime	225	288
Coal	288	291
Lime & Slate	291	320
Lime	320	371
Lime Broken	371	418
Waynesburg Coal	418	421
Slate	421	428
Lime	428	600
Slate	600	610
Lime	610	700
Brown Slate	700	706
Pittsburgh Coal	706	712
Lime	712	717
Slate	717	730
Lime	730	768
Red Rock	768	785
Slate & Shells	785	815
Sand	815	830
Red Rock	830	850
Slate & Shells	850	1044
Sand	1044	1068

Slate	1068	1078
Sand	1078	1095
Slate & Shells	1095	1175
Lime	1175	1207
Slate	1207	1230
Sand	1230	1272
Slate & Shells	1272	1332
Gas Sand	1332	1385
Slate	1385	1415
Broken Sand	1415	1459
Salt Sand	1459	1481
Slate	1481	1482
Salt Sand	1482	
TOTAL DEPTH		1482
Filled back up with chips	1492	1481
Set Baker Plug	1480	1478
TOTAL DEPTH		1478

Gas 25 1249
Gas at 1465' 24/10 Water in 2", 158,593
Gas 1465 to 1476' 100/10 Water in 3"
Test at 1479' 24/10 Water Pit Tube 4"
952,320 cu. ft.
Test at 1492' 16/10 Merc. in 2 1/2" 725,196
Test after 4" tubing run 32/10 W in 3"
638,987 cu. ft. at 1478'.



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Co.
Coal Operator or Owner
PO Box 100, Osage, WV 26543
Address

Consolidation Coal Co.
Coal Operator or Owner
PO Box 100, Osage, WV 26543
Address

Nasir Khan
Lease or Property Owner
110 West Ridge Blvd., Barlett, IL 60103
Address

Consolidation Coal Co.
Name of Well Operator
PO Box 100, Osage, WV 26543
Complete Address

Majorsville, WV
Well Location

Sandhill

District

Marshall

County

4124

Well No.

Nasir Khan

Farm

STATE INSPECTOR SUPERVISING PLUGGING

Randal K. Mick

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:

Nicky C. Hyre and Donald L. Hatfield being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of July 2000 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
			4 1/2" - 1474.12'	0
			8 5/8" - 0	1352'
			10 3/4" - 0	748'
Coal Seams		Description of Monument		
(Name)	Pittsburgh Coal 709' - 716'	7" casing with API #47-051-230 and completion		
(Name)		Date 7/28/2000		
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 28th day of July 2000

And further deponents saith not.


8/16/00
Nicky C. Hyre
Donald L. Hatfield

Sworn to and subscribed before me this 16th day of August 2000.

Lisa A. Albright
Notary Public

My commission expires:

2/11/2010



Permit No.

API#47-051-230

SEP 08 2000

MARS 0230