

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**WEST VIRGINIA LAND RESOURCES INC**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**WEST VIRGINIA LAND RESOURCES INC**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**LARRY C. WILLIAMS ET UX**  
Lease or Property Owner  
**1654 Fish Ridge, Cameron, WV 26033**  
Address

**WEST VIRGINIA LAND RESOURCES INC**  
Name of Well Operator  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Complete Address  
**CAMERON, WV 7.5'**  
Well Location  
**Liberty**  
District  
**Marshall**  
County  
**M-2103**  
Well No.  
**J. N. QUIGLEY**  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower


AFFIDAVIT 08/25/2026

STATE OF WEST VIRGINIA,  
County of Marshall ss:

**MATTHEW A. YEARSLEY** and **JOHN CAMPBELL** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 30<sup>th</sup> day of June 2026 and that the well was plugged in the following manner:

| Sand or Zone Record                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Filling Material | Casing/Tubing Size                                                                                                                                               | Casing Pulled | Casing Left In |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|----------------|
| Formation                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                  |                                                                                                                                                                  |               |                |
| Cleaned a 6 1/4" hole from surface to a 1766'. Cleaned inside 7" casing a 6 1/4" hole through the Pittsburgh Coal seam located from 813' to 820'. Made a diligent attempt to remove the 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Perforated the 7" and 8 5/8" casings at 1020', 970', 920', 870', 763', and 713'. Cemented the hole from 1766' to 1020' using 115 sacks of Expandable Cement. Cemented from 1020' to 850' using 55 sacks of Thixotropic Cement w/Green Dye and a Gas Blocker additive. Cut the 7" and 8 5/8" casings at 821', 820', 817', 815', 813', and 812'. Due to the extreme cement bond behind the 7" casing, no additional rips, perforations or cuts was pulled. | 7" Casing        | 0'                                                                                                                                                               | Unknown       |                |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 8 5/8"           | 0'                                                                                                                                                               | Unknown       |                |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 16" Conductor    | 0'                                                                                                                                                               | 20'           |                |
| <b>Cemented the hole from 850' to surface as follows:</b><br>From 850' to 613' using 45 sacks of Thixotropic Cement w/Green Dye additive. From 613' to surface using 95 sacks of Expandable Cement. Cement did circulate at surface. A total of 310 sacks were used to cement the hole from 1766' to surface. Left an unknown amount of 7" and 8 5/8" casings in the well. Left a total of 20' of 16" conductor from surface to 20'.                                                                                                                                                                                                                                                                                             |                  |                                                                                                                                                                  |               |                |
| Coal Seams                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  | Description of Monument                                                                                                                                          |               |                |
| Pittsburgh                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 813' to 820'     | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. |               |                |

... and that the work of plugging and filling said well was completed on the 9<sup>th</sup> day of July 2026



Sworn to and subscribed before me this 24<sup>th</sup> day of August 2026

My commission expires:

August 13, 2029

Matthew A Yearsley

Matthew A. Yearsley

John Campbell

John Campbell

Notary Public

Permit No. 47-051-00391-00-00

Well No. M-2103

Latitude: 39° 46' 59.5" N

Longitude: -80° 34' 50.8" W

09/18/2026

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J. N. Quigley Operator Well No.: M-2103  
LOCATION: Elevation: 1162.5' Quadrangle: Cameron, WV 7.5'  
District: Liberty County: Marshall  
Latitude: 39.78318349 Feet South of 39 Deg. 46 Min. 59.5 Sec.  
Longitude: -80.5807633 Feet West of 80 Deg. 34 Min. 50.8 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent Jay Hores Coal Operator \_\_\_\_\_  
Permit Issued Date 4/15/2026 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Marshall ss:

Matthew A. Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 30th day of June, 2026, and the well was plugged and filled in the following manner:

| TYPE                           | FROM  | TO      | PIPE REMOVED      | LEFT    |
|--------------------------------|-------|---------|-------------------|---------|
| Expandable Cement              | 1766' | 1020'   | 7" Casing 0'      | Unknown |
| Thixotropic Cement w/Green Dye | 1020' | 850'    | 8 5/8" Casing 0'  | Unknown |
| Thixotropic Cement w/Green Dye | 850'  | 613'    | 16" Conductor 20' | 20'     |
| Expandable Cement              | 613'  | Surface |                   |         |
|                                |       |         |                   |         |
|                                |       |         |                   |         |
|                                |       |         |                   |         |

RECEIVED  
Office of Oil and Gas

SEP 08 2026


WV Department of  
Environmental Protection

Description of monument: 77' of 7" casing w/ company name, well number, permit number, and date cemented and that the work of plugging and filling said well was completed on the 9th day of July, 2026.

And further deponents saith not. Matthew A Yearsley  
John Campbell

Sworn and subscribe before me this 24<sup>th</sup> day of August, 2026

My commission expires August 13, 2029  
Kerri McCormick  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Strader Gower Title: Oil & Gas Inspector  
8/25/2026

09/18/2026