

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO. - OHIO VALLEY OPERATIONS
Coal Operator or Owner
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Address

CONSOLIDATION COAL CO. - OHIO VALLEY OPERATIONS
Name of Well Operator
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Complete Address

CONSOLIDATION COAL CO. - OHIO VALLEY OPERATIONS
Coal Operator or Owner
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Address

MAJORSVILLE, WV 7.5'
Well Location
WEBSTER
District
MARSHALL
County
SGW-147
Well No.

CHARLES ALBERT WITSBERGER II
Lease or Property Owner
250 DRY RIDGE ROAD CAMERON, WV 26033
Address

CHARLES ALBERT WITSBERGER II
Farm

STATE INSPECTOR SUPERVISING PLUGGING

James Wickham
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of **MONONGALIA** ss:

MARK WILSON and **KEVIN WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of September, 2014 and that the well was plugged in the following manner:

| Sand or Zone Record Formation | Filling Material | Casing / Tubing Size | Casing Pulled | Casing Left In |
|--|------------------|--|---------------|----------------|
| Removed 1669' of 4 1/2" casing from Surface to 1669'. Removed 982' of 7" casing from Surface to 982'. Left 443' of 7" casing in the hole from 982' to 1425'. Cut remaining 7" casing at the following depths: 1300', 1197', and 1098'. Cemented bottom hole plug from 1669' to 896' with 140 sacks of Expandable Cement. Left 908' of 8 5/8" casing in the hole from Surface to 908'. Section milled 20' of 8 5/8" casing from 883' to 703' through the Pittsburgh Coal seam from 690' to 696'. Cut remaining 8 5/8" casing at the following depths: 894', 846', 794', and 742'. Left 20' of 16" conductor casing in the hole from Surface to 20'. | | 16" Conductor Casing | 0' | 20' |
| | | 8 5/8" Casing | 0' | 908' |
| | | 7" Casing | 982' | 445' |
| <u>Cemented hole from top of bottom hole plug at 896' back to the Surface as follows:</u> | | | | |
| From 896' to 590' with 10 sacks of Thixotropic Cement with green dye. From 590' to the surface with 140 sacks of Expandable Cement. Cement did circulate at the surface. | | | | |
| Coal Seams | | Description of Monument | | |
| Pittsburgh Coal | 690' to 696' | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker attached to the cement plug at ground level. | | |

RECEIVED
Office of Oil and Gas
DEC 17 2014
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 1st day of October, 2014

And further deponents saith not.

Mark Wilson
Mark Wilson


Kevin Wright
Kevin Wright

Sworn to and subscribed before me this 21 day of November 2014

Kara Beth Forst
Notary Public

My commission expires: 11/4/23

Permit No. 47-051-00549-P
Well No. SGW-147



12/19/2014