

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Merl G. Howard Operator Well No.: SGW-240

LOCATION: Elevation: 1282' Quadrangle: Valley Grove, WV
District: Sandhill County: Marshall
Latitude: 40.02 Feet South of 40 Deg. 01 Min. 15.40 Sec.
Longitude: -80.60 Feet West of -80 Deg. 36 Min. 16.17 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virginia Land Resources INC</u>	Coal Operator	<u>West Virginia Land Resources INC</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>7/9/2024</u>	or Owner	_____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:

Matthew A. Yearsley and Mark Wilson being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 11th day of April, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Gas Blocker	949'	521'	7" Casing	19'
Expanding	521'	Surface	10-3/4" Casing	678'
			16" Conductor Casing	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 22nd day of April, 2025.


And further deponents saith not. Matthew A. Yearsley

Mark Wilson

Sworn and subscribe before me this 29th day of May, 2025

My commission expires: August 13, 2029

Kerri A. McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Strader Gower Title: Oil & Gas Inspector

06/27/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC

Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554

Address

WEST VIRGINIA LAND RESOURCES INC

Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554

Address

BAIRD FAMILY TRUST

Lease or Property Owner

1531 STONE CHURCH RD WHEELING, WV 26003

Address

WEST VIRGINIA LAND RESOURCES INC

Name of Well Operator

1 BRIDGE STREET MONONGAH, WV 26554

Complete Address

VALLEY GROVE WV

Well Location

SANDHILL

District

MARSHALL

County

SGW-240

Well No.

MERL G. HOWARD

Farm

STATE INSPECTOR SUPERVISING PLUGGING STRADER GOWER

AFFIDAVIT

Strader Gower 6/03/2025


STATE OF WEST VIRGINIA,

County of MARSHALL ss:

MATTHEW A. YEARSLEY and MARK WILSON being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11th day of April, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 6 1/4" hole from surface to 949'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (721' - 728'). Made a diligent effort to remove 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Left 7" casing from surface to 19'. Left 10-3/4" casing from surface to 678'. Left 20' of 16" conductor in the hole from 20' to surface. <u>Cemented hole from 949' to surface as follows:</u> Cemented hole from 949' to 521' with 215 sacks of Thixotropic Cement with Gas Blocker Additive and Green Dye. Cemented hole from 521' back to surface with 160 sacks of Expandable Cement. Cement did circulate at surface. A total of 375 sacks of cement were used to fill the hole from 949' to surface.	7" Casing	0'	19'	
	10-3/4" Casing	0'	678'	
	16" Conductor Casing	0'	20'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	721' - 728'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at around level.		

... and that the work of plugging and filling said well was completed on the 22th day of April, 2025



Sworn to and subscribed before me this

29th day of May 2025

Matthew A. Yearsley

Matthew A. Yearsley

Mark Wilson

Mark Wilson

Kerri A. McCormick
Notary Public

My commission expires:

August 13 2029

Permit No. 47-051-00552

Well No. SGW-240

Latitude: 40° 01' 15.40"N

Longitude: -80° 36' 16.17"W

06/27/2025