

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: November 14th 2017
API #: 47-051-00573P

Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: LOUGH, MABEL L. Operator Well No.: 1595 (Leatherwood) Plugging (2017)

LOCATION: Elevation: 1227.02' Quadrangle: Cameron
District: Cameron County: Marshall
Latitude: 10.906 Feet South of: 39 Deg. 52 Min. 30 Sec.
Longitude: 7.294 Feet West of: 80 Deg. 30 Min. 00 Sec.

Well Type: OIL GAS X

Company: CNX Gas Company LLC
P.O. Box 1248
Jane Lew, WV 26378

Coal Operator:
or Owner See List on Page 2

Agent: Christopher Turner
Permit Issued Date: 5/9/2016

RECEIVED
Office of Oil and Gas
NOV 16 2017
WV Department of
Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Lewis ss:

Steve Spittler and Mike Lewis being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of April, 2017, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A Cement - 50 sks	2909'	2509'		
<u>4 1/2" csg</u>			<u>2500'</u>	
Class A Cement - 110 sks	2786'	1840'		
<u>6 5/8" csg</u>			<u>1215'</u>	<u>650'</u>
Perfed 8 1/4" csg every 100'	1220'	Surface	w/ 4 tag shots every 100'	
<u>8 1/4" csg</u>				<u>1220'</u>
Class A Cement - 520 sks	1836'	Surface		


Description of monument: 4 1/2" csg extending 48" above GL w/ company, well #, API #, & Plug Date.
and that the work of plugging and filling said well was completed on the 18th day of April, 2017.

NOTE:

And further deponents saith not.

Sworn and subscribe before me this 27th day of Oct, 2017

My commission expires: Sept. 26, 2021



Cindy L. Kovach
Notary Public

Affidavit reviewed by the Office of Oil and Gas

Jim Nielsen

Title: Oil & Gas Inspector

Created: (10/27/2017)

12/29/2017

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: ~~November 2~~ 14th 2017
API #: 47-051-00573P
Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

Farm Name: LOUGH, MABEL L.

Operator Well No.: 1595 (Leatherwood) Plugging
(2017)

COAL OPERATOR or OWNER

Coal Operator: Consolidation Coal Company
or Owner 1000 Consol Energy Drive
Canonsburg, PA 15317-6506

Coal Operator: Ronald Kasserman
or Owner 369 Pembroke Drive
Triadelphia, WV 26059

Created: (10/27/2017)
Permit Issued Date: 05/09/2016