

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: W. J. Bryan Operator Well No.: M-1743

LOCATION: Elevation: 1051.09' Quadrangle: Cameron  
District: Liberty County: Marshall  
Latitude: 39.78753 Feet South of 39 Deg. 47 Min. 30 Sec.  
Longitude: -80.53815 Feet West of 80 Deg. 30 Min. 00 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company: West Virginia Land Resources, LLC. Coal Operator West Virginia Land Resources, LLC.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent Jay Hores Coal Operator \_\_\_\_\_  
Permit Issued Date 10/15/2025 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Marshall ss:

Mark Wilson and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 11th day of December, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement	3006'	2390'	4 1/2" Casing 2390'	616'
Expandable Cement	2390'	992'	7" Casing 994'	950'
Thixotropic Cement	992'	585'	20" Conductor 0'	20'
Expandable Cement	585'	Surface		

RECEIVED  
Office of Oil and Gas  
FEB 17 2026  
WV Department of  
Environmental Protection


Description of monument: 77" of 7" casing with company name, well#, API#, and date cemented. and that the work of plugging and filling said well was completed on the 1st day of January, 2026.

And further deponents saith not. Matthew A. Yearsley

Mark Wilson

Sworn and subscribe before me this 4th day of February, 2026

My commission expires: August 13, 2029 Kerri McCormick  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Strader Gower Title: OIL & GAS INSPECTOR

02/20/2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

JOHN E ARTIMEZ JR ET AL (C/O LANCE JOHNSON)  
Lease or Property Owner  
121 White Bell Circle, Wellsburg, WV 26070  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041  
Complete Address  
CAMERON, WV 7.5'  
Well Location  
Liberty  
District  
Marshall  
County  
M-1743  
Well No.  
W. J. BRYAN  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Strader Gower  
AFFIDAVIT *Strader Gower*  
02/05/2026

STATE OF WEST VIRGINIA,  
County of MARSHALL ss:

MATTHEW A. YEARSLEY and MARK WILSON being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11<sup>th</sup> day of December, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
<b>Formation</b>				
Cleaned hole inside of the 4 1/2" casing from surface to 3,006'. Perforated 4 1/2" casing at 2990', 2790', 2590' and 2390' using 6 shots at each location for a total of 24 shots. Cemented hole from 3006' to 2390' using 40 sacks of Expandable Cement with Gas Blocker additive. Removed 2390' of 4 1/2" casing from surface to 2390'. Cut 7" casing at 1192', 1392', 1592' and 1992'. Removed 994' of 7" casing from 994' to surface. Made a diligent attempt to remove the remaining 7" casing from 994' to 1944' by pulling 150% of string weight. All attempts were unsuccessful. Cleaned hole from surface to 319' using a 12 1/4" bit. Reduced bit size to a 9 7/8" and cleaned hole from 319' to 944' and through the Pittsburgh Coal Seam located from 785' to 792'. Reduced bit size to a 6 1/4" and cleaned hole from 944' to top of cement plug at 2390'. Left 20' of 20" Conductor from surface to 20'.	4 1/2" Casing 7" Casing 20" Conductor	2390' 994' 0'	616' 950' 20'	
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>785' to 792'</u>	<u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 13<sup>th</sup> day of January 2026



Matthew A. Yearsley  
Matthew A. Yearsley

Mark Wilson  
Mark Wilson

Sworn to and subscribed before me this

*4th* day of *February* 2026

*Kerri McCormick*  
Notary Public

My commission expires:

*August 13, 2029*

Permit No. 47-051-00578  
Well No. M-1743  
Latitude: 39° 47' 30" N  
Longitude: -80° 30' 00" W

RECEIVED  
Office of Oil and Gas  
**FEB 17 2026**  
WV Department of  
Environmental Protection

02/20/2026