

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.B. Miller Operator Well No.: M-1513

LOCATION: Elevation: 1273' Quadrangle: Cameron WV, PA
District: Liberty County: Marshall
Latitude: _____ Feet South of 39 Deg. 49 Min. 15.47 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 19.33 Sec.

Well Type: OIL _____ GAS _____

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 11/30/2021 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of August, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	3019'	2005'	2027' - 4 1/2" Casing	Unknown
Expandable Cement	2005'	1075'	1428' - 7" Casing	552'
Thixotropic Cement w/ Green Dye	1075'	667'	1094' - 8 5/8" Casing	106'
Expandable Cement	667'	Surface	0' - 24" Conductor Pipe	12'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 26th day of August, 2022.

And further deponents saith not. Matthew Yearsley

Kevin S. Wright

Sworn and subscribe before me this 29 day of September, 2022



My commission expires: June 8, 2027

Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Strader Gower 10/03/2022

Title: Oil & Gas 09/24/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
RANDY L. & CHARLENE D. ROSS
Lease or Property Owner
1334 GREEN VALLY RD. CAMERON, WV 26033
Address

CONSOLIDATION COAL COMPANY
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
LIBERTY
District
MARSHALL
County
M-1513
Well No.
J. B. Miller
Farm

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower 10/03/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17th day of August, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
<p>Cleaned a 3 1/8" hole through the 4 1/2" casing from the surface to the attainable bottom at 3019'. Removed 2027' of 4 1/2" casing from surface to 2027'. Left an unknown amount of 4 1/2" casing in the hole from 2027' to unknown depth. Perforated the remaining 4 1/2" casing with 6 shots at each of the following depths: 3004', 2806', 2605', 2404' and 2206'. Cemented the bottom hole from 3019' to 2005' with 65 sacks of Expandable Cement with a Gas Blocker additive. Removed 1425' of 7" casing from 24' to 1449'. Attempted to remove the remaining 7" casing by pulling 150% of string weight but all attempts were unsuccessful. Left 552' of 7" casing in the hole from 1452' to 2001'. Cut the remaining 7" casing at 1658' and 1860'. Removed 1094' of 8 5/8" casing from the surface to 1094'. Attempted to remove the remaining 8 5/8" casing by pulling 150% of string weight but all attempts were unsuccessful. Left 106' of 8 5/8" casing in the hole from 1094' to 1200'. Cleaned a 12 1/4" hole from the surface to 263'. Reduced the hole to 9 7/8" at 263'. Cleaned a 9 7/8" hole from 263' to the top of the remaining 8 5/8" casing at 1094'. Reduced the hole to 7 7/8" at 1094'. Cleaned a 7 7/8" hole from 1094' to the top of the remaining 7" casing at 1449'. Reduced the hole to 6 1/4" at 1449'. Cleaned a 6 1/4" hole from 1449' to the top of the bottom hole plug at 2005'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (867.5' - 874.3'). Left 12' of a 24" conductor in hole from surface to 12'. Cemented the hole from 2005' back to the surface as follows: From 2005' to 1075' with 210 sacks of Expandable Cement. From 1075' to 667' with 195 sacks of Thixotropic Cement with Green Dye. From 667' to the surface with 360 sacks of Expandable Cement. Cement did circulate at surface.</p>	4 1/2" Casing	2027'	Unknown	
	7" Casing	1428'	552'	
	8 5/8" Casing	0'	106'	
	24" Conductor	0'	12'	
Coal Seams	Description of Monument			
Pittsburgh	867.5' - 874.3'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 29th day of August, 2022

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright


03/24/2023

Sworn to and subscribed before me this 29 day of September, 2022

[Signature]
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-051-00587
Well No. M-1513
Latitude: 39° 49' 15.47"N
Longitude: -80° 32' 19.33"W