

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Richards Operator Well No.: M-1079

LOCATION: Elevation: 1426.11 Quadrangle: Cameron, WV 7.5'
District: Liberty County: Marshall
Latitude: _____ Feet South of 39 Deg. 48 Min. 51.48 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 54.69 Sec.

Well Type: OIL _____ GAS X

Company Consolidation Coal Company Coal Operator Consolidation Coal Company
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent Dave Roddy Coal Operator _____
Permit Issued Date 11/30/2021 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of June, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	3064'	1242'	4 1/2" Casing - 2754'	Unknown
Thixotropic Cement w/ Green Dye	1242'	834'	7' Casing - 1515'	617'
Expandable Cement	834'	Surface	10 3/4" Casing - 1048'	362'
			16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 7th day of July, 2022.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 23 day of August, 2022

My commission expires: June 8, 2027
Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Strader Gover Title: Inspector Oil & Gas

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

LATICHA M. RICHARDS
Lease or Property Owner
146 RICHARDS LANE CAMERON, WV 26033
Address

CONSOLIDATION COAL COMPANY
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
CAMERON WV 7.5'

Well Location

LIBERTY

District

MARSHALL

County

M-1079

Well No.

RICHARDS

Farm

STATE INSPECTOR SUPERVISING PLUGGING

Strader Goner

8/24/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of June, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 2754' of 4 1/2" casing from the surface to 2754'. Left an unknown amount of 4 1/2" casing in the hole from 2754' to unknown depth. Cleaned a 2 7/8" hole through the 4 1/2" casing from the surface to 3064'. Tagged a plug at 3064'. Cemented the bottom hole from 3064' back to 2275' with 130 sacks of Expandable Cement with a Gas Blocker additive. Tagged top of bottom hole plug at 2275'. Removed 1515' of 7" casing from surface to 1515'. Attempted to remove remaining 7" casing by 150% of the string weight but all attempts were unsuccessful. Left 617' of 7" casing in hole from 1515' to 2132'. Cut the remaining 7" casing at 1628', 1718', 1818', 1925' and 2028'. Removed 1031' of 10 3/4" casing from surface to 1031'. Pilot milled 17' of 10 3/4" casing through the Pittsburgh Coal Seam (1034.9' - 1041.5') from 1031' to 1048'. Left 362' of 10 3/4" casing in the hole from 1048' to 1410'. Cut the remaining 10 3/4" casing at 1072', 1091', 1141', 1191' and 1251'. Cleaned a 12 1/4" hole from the surface to 1048'. Tagged the remaining 10 3/4" casing at 1048'. Reduced the hole to 9 7/8" at 1048'. Cleaned a 9 7/8" hole from 1048' to the top of the remaining 7" casing at 1515'. Reduced the hole to 6 1/4" at 1515'. Cleaned a 6 1/4" hole from 1515' to the top of the bottom hole plug at 2142'. Cleaned a 12 1/4" hole through the Pittsburgh Coal Seam (1034.9' - 1041.5'). Left 20' of a 16" conductor in the hole from surface to 20'. Cemented the hole from 2275' back to surface as follows: From 2275' to 1242' with 250 sacks of Expandable Cement with a Gas Blocker additive. Tagged top of cement plug at 1242'. From 1242' back to 834' with 285 sacks of Thixotropic Cement with Green Dye and from 834' back to the surface with 600 sacks of Expandable Cement. Cement did circulate at the surface.	4 1/2" Casing 7" Casing 10 3/4" Casing 16" Conductor	2754' 1515' 0' 0'	Unknown 617' 362' 20'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1034.9' - 1041.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of July, 2022

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright


Sworn to and subscribed before me this 23 day of August 2022

01/06/2023

[Signature]
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-051-00605

Well No. M-1079

Latitude: 39° 48' 51.14"N

Longitude: -80° 32' 54.69"W