

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: James Bane Operator Well No.: M-1611

LOCATION: Elevation: 1327.23' Quadrangle: Cameron WV, PA
District: Cameron County: Marshall
Latitude: _____ Feet South of 39 Deg. 52 Min. 13.05 Sec.
Longitude: _____ Feet West of -80. Deg. 33 Min. 23.46 Sec.

Well Type: OIL X GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 01/08/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 3rd day of March, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	5141'	1290'		
Thixotropic Cement w/ Green Dye	1290'	640'		
Expandable Cement	640'	Surface		
4 1/2" Casing	1235'	5045'	1235'	3810'
8 5/8" Casing	Surface	1507'	Milled 28'	1479'

Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 19th day of March, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 25th day of Mar, 2021

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: inspector 05/11/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

JAMES ERCIL BANE EST ET AL (C/O CHARLES E. PHILLIPS)
Lease or Property Owner
1161 ROCK HILL LANE WHEELING, WV 26003
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
CAMERON WV, PA

Well Location
CAMERON

District

MARSHALL

County

M-1611

Well No.

JAMES BANE

Farm

STATE INSPECTOR SUPERVISING PLUGGING

Barry Stalip

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of March, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned out existing 4 1/2" casing with 2 3/8" drill pipe from the surface to 5141'. Cement bond log indicated that the 4 1/2" casing was cemented in the hole from 5045' to 1235'. Cemented the bottom hole from 5141' to 1290' with 240 sacks of Expandable Cement with a gas blocker additive. Removed 1235' of 4 1/2" casing from the surface to 1235'. Left 3810' of 4 1/2" in the hole from 5045' to 1235'. Due to cement bonding, 1507' of 8 5/8" casing was left in the hole from the surface to 1507'. The depth for the bottom of the 8 5/8" casing was taken from the original well record. Section milled 28' window in 8 5/8" casing from 828' to 856'. No casing was left through the Pittsburgh Coal Seam (840' - 846').		4 1/2" Casing	1235"	3810'
			8 5/8" Casing	0'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	840' - 846'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of March, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 25th day of Mar, 2021

Thomas J. Sullivan 05/11/2023
Notary Public

My commission expires: 09/15/22

Permit No. 47-051-00689
Well No. M-1611
Latitude: 39° 52' 13.05"N
Longitude: -80° 33' 23.46"W