

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

MCELROY COAL COMPANY
Coal Operator or Owner
RD. 4, Box 425 Moundsville, WV 26041-9802
Address

MCELROY COAL COMPANY
Coal Operator or Owner
RD. 4, Box 425 Moundsville, WV 26041-9802
Address

MCELROY COAL COMPANY
Lease or Property Owner
1000 Consol Energy Drive Canonsburg, PA 15317
Address

MCELROY COAL COMPANY
Name of Well Operator
RD. 4, Box 245 Moundsville, WV 26041-9802
Complete Address

CAMERON, WV-PA 7.5
Well Location

Liberty
District

MARSHALL
County

M-474
Well No.

J. M. EAGAN
Farm

M-474
Well No.

J. M. EAGAN
Farm

J. M. EAGAN
Farm

RECEIVED
Office of Oil & Gas

STATE INSPECTOR SUPERVISING PLUGGING [Signature]

DEC 21 2011

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

WV Department of
Environmental Protection

MARK WILSON and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 31st day of October, 2011 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
<u>Formation</u>				
<u>This is an addendum to the plugging affidavit dated 4/2/2010.</u>				
	Drilled cement out of 4 1/2" casing from the surface to 2188' with a 3 7/8" bit. Section milled an 8' window in the 4 1/2" casing from 2063' to 2071'. Cemented bottom hole from 2188' to 1600' with 45 sacks of Thixotropic Cement.	10 3/4"	0'	157'
	Sand cut 4 1/2", 7" and 8 5/8" casings at the following depths; 1400', 1380', 1358', 1340', 1320', 1291', 950' and 935'.	8 5/8"	0'	1240'
	<u>Cemented hole from 2188' to surface as follows:</u>	7"	0'	1961'
	From 2188' to 1600' with 45 sacks of Thixotropic Cement.	4 1/2"	0'	2898'
	From 1600' to 1450' with 50 sacks of Thixotropic Cement.			
	From 1450' to 60' with 125 sacks of Thixotropic Cement.			
	From 60' to surface with 10 sacks of Expendable cement.			
	A total of 230 sacks of cement were used to fill the hole from 2188' to surface. Cement did circulate at the surface.			
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>Pittsburgh</u>	(864' to 870')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		

... And that the work of plugging and filling said well was completed on the 28th day of November, 2011

And further deponents saith not.

[Signature]
Mark Wilson


[Signature]
Kevin S. Wright

Sworn to and subscribed before me this 15th day of December, 2011

[Signature]
Notary Public

My commission expires:

March 18, 2020



Permit No. 47-051-00744-P
Well No. M-474