

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: W.A. Dowler Operator Well No.: M-1608

LOCATION: Elevation: 1322' Quadrangle: Cameron WW, PA
District: Liberty County: Marshall
Latitude: _____ Feet South of 39 Deg. 48 Min. 57.64 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 17.36 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 05/25/2021 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	2253'	1172'		
Thixotropic Cement w/ Green Dye	1172'	724'		
Expandable Cement	724'	0'		
2 3/8" Tubing	2253'	Unknown	2253'	Unknown
7" Casing	1844'	2054'	1844'	210'
10 3/4" Casing	Surface	1300'	0' (Multiple Cuts)	1300'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 30th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright



Sworn and subscribe before me this 16th day of Aug, 2021

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: 8-17-21 inspector
03/03/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
HARMEN E BROWN ET UX (C/O RUTH E RIGGLE)
Lease or Property Owner
875 DRAGON HWY CAMERON, WV 26033
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
LIBERTY
District
MARSHALL
County
M-1608
Well No.
W.A. DOWLER
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Ray Stiles 8-17-21

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15th day of July, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 2253' of 2 3/8" tubing from surface to 2253'. Left an unknown amount of 2 3/8" tubing in the hole from 2253' to an unknown depth. Cemented the bottom hole from 2253' to 2054' with 40 sacks of Expandable Cement with a Gas Blocker additive. Removed 1844' of 7" casing from the surface to 1844'. Left 210' of 7" casing in the hole from 1844' to 2054'. Cut remaining 7" casing at 1950'. Cleaned a 9 7/8" hole from the surface to 1844'. Reduced the hole to 6 1/4" at 1844'. Cleaned the hole with a 6 1/4" bit from 1844' to the top of the bottom hole plug at 2054'. Cemented the hole from 2054' back to 1172' with 320 sacks of Expanding Cement with a Gas Blocker additive. Attempted to remove existing 10 3/4" casing by pulling 150% of string weight. All attempts to remove 10 3/4" casing were unsuccessful. Left 1300' of 10 3/4" casing in the hole from the surface to 1300'. Cut remaining 10 3/4" casing at 1090', 990', 950', 945', 941', 940', 938.5', 937', 935.5', 934', 933', 932', 931', 930', 929', 923', 883', 833'. 10 3/4" casing was previously ripped at 1040'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (933' - 940'). Left 20' of 16" conductor in the hole from the surface to 20'.		2 3/8" Tubing 7" Casing 10 3/4" Casing 16" Conductor	2,253' 1,844' 0' 0'	Unknown 210' 1,300' 20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	933' - 940'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 30th day of July, 2021


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this *16th* day of *Aug, 2021*

[Signature] 03/03/2023
Notary Public

My commission expires: *09/15/22*

Permit No. 47-051-00745
Well No. M-1608
Latitude: 39° 48' 57.64"N
Longitude: -80° 32' 17.36"W