

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: W. A. Dowler Operator Well No.: M-1607

LOCATION: Elevation: 1305' Quadrangle: Cameron WV, PA
District: Liberty County: Marshall
Latitude: _____ Feet South of 39 Deg. 48 Min. 55.55 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 01.79 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 05/24/2021 _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of June, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement	3020'	2880'	3 1/2" Casing - Pulled 2255'	Unknown
Gel Spacer	2880'	2250'	7" Casing - Pulled 1550'	500'
Expandable Cement w/ Gas Blocker	2250'	1342'	8 5/8" Casing - Pulled 1160'	200' - Cut at 1260'
Expandable Cement	1342'	1143'	16" Conductor - Pulled 0'	20'
Thixotropic Cement	1143'	735'		
Expandable Cement	735'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 12th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 10th day of Aug, 2021

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: inspector 05/19/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
HARMEN E BROWN ET UX (C/O RUTH E RIGGLE)
Lease or Property Owner
875 DRAGON HWY CAMERON, WV 26033
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
LIBERTY
District
MARSHALL
County
M-1607
Well No.
W.A. DOWLER
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Bang Stiles 8-17-21

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17th day of June, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned out 3 1/2" casing w/ 1 1/2" tubing from the surface to 3020'. Tagged plug at 3,020'. Cemented bottom hole from 3020' to 2880' with 20 sacks of Expandable Cement. Wireline cut 3 1/2" casing at 2860'. 3 1/2" casing would not move. Run free point log. Wireline cut 3 1/2" casing at 2,255'. Removed 3 1/2' casing from the surface to 2255'. Left an unknown amount of 3 1/2' casing in the hole from 2255' to an unknown depth. Removed 1550' of 7" casing from surface to 1550'. Left 500' of 7" casing in the hole from 1550' to 2050'. Cut remaining 7" casing at 1950', 1850', 1750' and 1648'. Placed a 6% gel spacer in the hole from 2880' to 2250'. Cemented hole from 2250' to 1342' with 150 sacks of Expandable Cement with a gas blocker additive. Removed 1160' of 8 5/8" casing from the surface to 1160'. Left 200' of 8 5/8" casing in the hole from 1160' to 1360'. Cut remaining 8 5/8" casing at 1260'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (935.5' - 942.3'). Left 20' of 16" conductor in the hole from 20' to surface.		2 3/8" Tubing	2,255'	Unknown
		7" Casing	1,550'	500'
		8 5/8" Casing	1,160'	200'
		16" Conductor	0'	20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>935.5' - 942.3'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of July, 2021

And further deponents saith not.



Sworn to and subscribed before me this *10th* day of *Aug, 2021*

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature]

Notary Public

05/11/2023

My commission expires: *09/15/22*

Permit No. 47-051-00747
Well No. M-1607
Latitude: 39° 48' 55.55"N
Longitude: -80° 32' 01.79"W