

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Co.
Coal Operator or Owner
PO Box 100, Osage, WV 26543
Address

Consolidation Coal Co.
Coal Operator or Owner
PO Box 100, Osage, WV 26543
Address

Larry J. Whetzel
Lease or Property Owner
Rd #1 Box 79, Glen Easton, WV 26039
Address

Consolidation Coal Co.
Name of Well Operator
PO Box 100, Osage, WV 26543

Complete Address
Glen Easton, WV

Well Location

Meade

District

Marshall

County

M-59

Well No.

Larry J. Whetzel

Farm

STATE INSPECTOR SUPERVISING PLUGGING

Randoe Mick

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:

Robert L. Steel and Donald L. Hatfield being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of February and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Plugs Used	Casing Pulled	Casing Left In
Formation		Size & Kind		
Clean hole with 9 7/8" bit from surface to 1139'. Top 10" casing. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 1139' to 1352'. Left 10" casing in hole from 1139' to 1286'. Cemented 9 7/8" hole thru Pittsburgh Coal 882' thru 888'. Cemented well with solid cement plug from 1352' back to surface.		1352' to 1088' - 35/65 poz 1088' to 682' - thixotropic 682 to surface - 35/65 poz	0	147'
Coal Seams		Description of Monument		
(Name)	Pittsburgh Coal 882' thru 888'	7" well marker with well completion date of		
(Name)		2/18/2000 and API #47-051-084P		
(Name)				
(Name)				

[Signature] 3/20/00

... and that the work of plugging and filling said well was completed on the 18th day of February 2000


And further deponents saith not.

Robert L. Steel
Donald L. Hatfield

Sworn to and subscribed before me this 28th day of February

Kathleen M. Blake
Notary Public

My commission expires:



Permit No.

API #47-051-084P

051-00847P

MAR 13 2000

MARS 0847 P