

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

McElroy Coal Co.
Coal Operator or Owner
R.D. #4 Box 425, Moundsville, WV 26041
Address
McElroy Coal Company
Coal Operator or Owner
R.D. #4 Box 425, Moundsville, WV 26041
Address
Raymond D. Dobbs
Lease or Property Owner
508 Midway Lane, Glen Easton, WV 26038
Address

Consolidation Coal Company
Name of Well Operator
PO Box 100, Osage, WV 26543
Complete Address
Glen Easton, WV
Well Location
Meade
District
Marshall
County
M50
Well No.
Raymond D. Dobbs
Farm

STATE INSPECTOR SUPERVISING PLUGGING

[Handwritten Signature]
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:

Robert L. Steel and Donald L. Hatfield being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of February 2000 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
	Cleaned hole with 9 7/8" bit from surface to 1190'. Trouble with steel junk from 1091' to 1190'. Cleaned 9 7/8" through Pittsburgh Coal from 967' to 974'. Cemented hole from 1190' back to surface.	1190' to 867' with 251 sks Thix and 867' to surface with 580 sks of 35/65 Pox Mix.	0	0
Coal Seams	Description of Monument			
(Name)	Pittsburgh Coal - 967' to 974'	7" casing with completion date and		
(Name)		API#47-051-848P		
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 10th day of March 2000


And further deponents saith not.

[Handwritten Signatures]
Robert L. Steel
Donald L. Hatfield

Sworn to and subscribed before me this 11th day of March 2000.

[Handwritten Signature]
Lisa A. Albright
Notary Public

My commission expires:
February 11, 2010



Permit No.
API#47-051-848P

APR 28 2000

MARS 0848P