



West Virginia Department of Environmental Protection
Office of Oil and Gas
WELL LOCATION FORM: GPS

API: 47-49-51-00910P WELL NO.: M-75

FARM NAME: W. J. Booker

RESPONSIBLE PARTY NAME: _____

COUNTY: Marshall DISTRICT: Meade

QUADRANGLE: Glen Easton 7.5"

SURFACE OWNER: Richard W. Byres

ROYALTY OWNER: _____

UTM GPS NORTHING: 4403552.7m

UTM GPS EASTING: 528939.7m GPS ELEVATION: 765.65'

The Responsible Party named above has chosen to submit GPS coordinates in lieu of preparing a new well location plat for a plugging permit on the above well. The Office of Oil and Gas will not accept GPS coordinates that do not meet the following requirements:

1. Datum: NAD 1983, Zone: 17 North, Coordinate Units: meters, Altitude: height above mean sea level (MSL) – meters.

2. Accuracy to Datum – 3.05 meters

3. Data Collection Method:

Survey grade GPS ____ : Post Processed Differential 0.01m
Real-Time Differential ____

Mapping Grade GPS ____ : Post Processed Differential ____
Real-Time Differential ____

I the undersigned, hereby certify this data is correct to the best of my knowledge and belief and shows all the information required by law and the regulations issued and prescribed by the Office of Oil and Gas.

[Signature] P.S. #2002

Professional Surveyor

Title

Signature
May 14, 2003

Date

75' loc calc from
WGS 80 coord program

0.58 S 34° 47' 30"
1.97 W 80° 37' 30"

might be 051 3020 (?)

JUL 18 2003

MARS 0910

5100910P

FILE COPY

MSHA: (SENT) 9-4-03
Log + copy

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Co./McElroy Coal Co.
Coal Operator or Owner
1 Bridge Street, Monongah, WV 26554
Address

Consolidation Coal Co./McElroy Coal Company
Coal Operator or Owner
1 Bridge Street, Monongah, WV 26554
Address
Richard W. Byers
Lease or Property Owner
Rd 5, Box 124B, Cameron WV 26033
Address

Consolidation Coal Co.
Name of Well Operator
1 Bridge Street, Monongah, WV 26554
Complete Address
Glen Easton 7.5'
Well Location
Meade
District
Marshall
County
M-75
Well No.
Richard W. Byers
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Terry Urban* Terry Urban

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of _____ ss:

Mike Mitchell and Kevin Wright, being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the August 8, 2003 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
	Cleaned 12 1/4" hole from surface to 705. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 705' to 990'. Pulled 10 3/4" casing from 664' to 743'. Cleaned 12 1/4" hole through Pittsburgh Coal which is from 479' to 486'. Cemented hole solid from 990' back to surface. Cemented well with solid plug from 990' to 686' with Hi-yield lite cement, cement from 686' to 379' with 230 sacks of THIX with RED Dye cement and from 379' to surface with Hi-yield lite cement. Used a total of 315 sacks of Hi-yield lite cement in well. <u>Cement did circulate.</u> Left 18' of 16" conductor at surface.		16" 10 3/4"	18' 212'
Coal Seams (Name)	Description of Monument			
	Pittsburgh Coal - 479" to 486"			
	7" well marker, 77" long with Consol Coal Co.,			
	Well number, permit number, date and solid plug			
	Stated on 7" casing. Well marker will be			
	Attached to solid cement plug at ground level.			

... and that the work of plugging and filling said well was completed on August 19, 2003.


And further deponents saith not.

Mike Mitchell
Mike Mitchell
Kevin Wright
Kevin Wright

Sworn to and subscribed before me this the 29th Day of August, 2003

Vicki L. Cayton
Notary Public

My commission expires:



Permit Number: 47-51-00910-P
(Well # M-75)

MAY 19 2006

MARS 0910-P