

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041  
Address

KENNETH WAYNE STEELE  
Lease or Property Owner  
350 E. EASTON RD. CRESTON, OH 44217  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041  
Complete Address

CAMERON WV 7.5'  
Well Location  
LIBERTY  
District  
MARSHALL  
County  
M-385  
Well No.

STEELE, KENNETH  
Farm

STATE INSPECTOR SUPERVISING PLUGGING



AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MICHAEL CAMPBELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22<sup>nd</sup> day of October, 2015 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 409'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 409' to 1249'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1041' to 1047'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 1249' to 1301'. Tagged solid plug at 1301'. Left 20' of 16" conductor casing in the hole from Surface to 20'.		16" Casing	0'	20'
<b>Cemented from 1301' back to the Surface as follows:</b> From 1301' back to the Surface with 755 sacks of Expandable Cement. Cement did circulate at the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	(1041' - 1047')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		

RECEIVED  
Office of Oil and Gas  
JAN 04 2016  
WV Department of  
Environmental Protection

... and that the work of plugging and filling said well was completed on the 4<sup>th</sup> day of November, 2015.

And further deponents saith not.


Michael Campbell  
Michael Campbell

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 9<sup>th</sup> day of Dec 2015

Carol A Mayle  
Notary Public

My commission expires: 9-12-17



Permit No. 47-51-00971-P  
Well No. M-385