

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: O. E. Burge Operator Well No.: M-1527B

LOCATION: Elevation: 1223' Quadrangle: Cameron WV, PA
District: Cameron County: Marshall
Latitude: _____ Feet South of 30 Deg. 49 Min. 38.64 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 25.16 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 03/06/2023 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18th day of July, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	5582'	1700'	5/8" Sucker Rods - 5542'	0'
Expandable Cement	1700'	1225'	2 3/8" Tubing - 5562'	0'
Thixotropic Cement w/ Green Dye	1225'	651'	4 1/2" Casing - 1685'	2398'
Expandable Cement	651'	Surface	7" Casing - 865'	580' (Cuts at 924.5', 974.5' and 1030')
			9 5/8" Casing	320'
			16" Conductor Pipe - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 1st day of August, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 16th day of Aug, 2023

My commission expires: 09/15/27

Notary Public

RECEIVED
Office of Oil and Gas
SEP 23 2023

Affidavit reviewed by the Office of Oil and Gas: Stander Gower Title: Oil & Gas Inspector

WV Department of Environmental Protection
10/20/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
DENNIS L. & MONA R. COE
Lease or Property Owner
1684 GREEN VALLEY RD. CAMERON, WV 26033
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
CAMERON WV, PA
Well Location
CAMERON
District
MARSHALL
County
M-1527B
Well No.
O. E. BURGE
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Shirley Gower

8/17/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of July, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Removed all 5542' of 5/8" sucker rods. Removed all 5562' of 2 3/8" tubing. Run cement bond log on existing 4 1/2" casing. Cement bond log indicated that the 4 1/2" casing was cemented up to 1700'. Cemented the bottom hole from 5582' to 1700' with 230 sacks of Expandable Cement with a Gas Blocker additive. Tagged top of bottom hole plug at 1700'. Removed 1685' of 4 1/2" casing from the surface to 1685'. Due to cement bonding 2398' of 4 1/2" casing was left in the hole from 1685' to 4083'. Cleaned a 6 1/4" hole through existing 7" casing from the surface to the top of the remaining 4 1/2" casing at 1685'. Removed 865' of 7" casing from the surface to 865'. A diligent effort was made to remove the remaining 7" casing by pulling 150% of the string weight but all efforts were unsuccessful due to cement bonding. Left 580' of 7" casing in the hole from 865' to 1445'. Cut remaining 7" casing at each of the following depths; 1030', 974.5' and 924.5'. Cleaned a 7 7/8" hole through existing 9 5/8" casing from the surface to the top of the remaining 7" casing at 865'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (817.5' - 824.5').	5/8" Sucker Rods	5542'	0'
		2 3/8" Tubing	5562'	0'
		4 1/2" Casing	1685'	2398'
		7" Casing	865'	580'
		9 5/8" Casing	0'	320'
		16" Conductor	0'	20'
CONTINUED ON PAGE 2				
Coal Seams		Description of Monument		
Pittsburgh	817.5' - 824.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1st day of August, 2023

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley


Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 16th day of AUG, 2023

[Signature]
Notary Public

My commission expires:



Permit No. 47-051-01054
Well No. M-1527B
Latitude: 39° 49' 38.64"N
Longitude: -80° 31' 25.16"W

RECEIVED
Office of Oil and Gas

SEP 23 2023

WV Department of
Environmental Protection

10/20/2023