

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner

1 BRIDGE STREET MONONGAH, WV 26554
Address

JESSIE C. FLETCHER ANTILL & KELBY W. ANTILL
Lease or Property Owner

327 FRESH AIR LN, CAMREON, WV 26033
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator

1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
Big Run, WV 7.5'

Well Location

CAMERON

District

MARSHALL

County

Fletcher 1

Well No.

Mark W. & Carol S. Fletcher
Farm

STATE INSPECTOR SUPERVISING PLUGGING STRADER GOWER

AFFIDAVIT *Strader Gower*
07/06/2026


STATE OF WEST VIRGINIA,

County of Marshall ss:

Matthew A Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22nd day of April 2026 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned the hole from surface to approved attainable bottom at 3147'. Removed 1475' of 4 1/2" casing from surface to 1475'. Left 1690' of 4 1/2" casing from 1475' to 3165'. Made a diligent attempt to remove the remaining 4 1/2" casing by pulling 150% of the string weight. All attempts were unsuccessful due to extreme cement bonding. Per the well record, 4 1/2" casing was previously perforated at the following depths 3110', 3087', 2970', 2057' and 2047'. Cemented from the WVDEP approved attainable bottom at 3147' to 2423' using 40 sacks of Expandable Cement with a Gas Blocker additive. Due to extreme cement bond behind the 4 1/2" casing, no additional cuts, rips or perforations were required. Cemented the hole from 2423' to 1480' using 60 sacks of Expandable Cement. Made a diligent attempt to remove the 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Perforated the 7" casing using 6 shots at 1415'. No additional cuts, rips or perforations were made due to the extreme cement bond on the 7" casing. Cuts were made in the 7" casing at the following depths: 1223.5', 1173.5', 1123.5', 1073.5', 1033.5', 1028.5', 1024.5', 1023.5', 1022', 1020.5', 1019', 1017.5', 1016.8', 1015.8', 1011.8', 1006.8', 966.8' and 916.8' through the Pittsburgh Coal seam located from 1016.8' to 1023.5'. Left a total of 1715' of 7" casing from 1715' to surface. Made a diligent attempt to remove the 9 5/8" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left a total of 311' of 9 5/8" casing from 311' to surface.				
Cemented the hole from 1480' to surface as follows: From 1480' to 793' using 130 sacks of Thixotropic Cement with a Green Dye additive. From 793' to surface using 180 sacks of Expandable Cement. Cement did circulate at surface. A total of 410 sacks were used to cement the hole from 3147' to surface. Left a total of 10' of 16" conductor from 10' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1016.8' to 1023.5'</u>	<u>77" of 7" casing w/ company name, well number,</u>		
		<u>permit number and date cemented stated on 7"</u>		
		<u>casing. Well marker will be attached to cement</u>		
		<u>plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 18th day of May 2026



Sworn to and subscribed before me this 2nd day of July 2026

My commission expires:

August 13, 2029

Matthew A Yearsley

Matthew A. Yearsley

John Campbell

John Campbell

Kerri McCormick
Notary Public

Permit No. 47-051-01106-00-00
Well No. Fletcher 1
Latitude: 39.84432 N
Longitude: -80.63404 W

RECEIVED
Office of Oil and Gas

JUL 20 2026

WV Department of
Environmental Protection

07/31/2026

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fletcher, Mark W. & Carol S. Operator Well No.: Fletcher 1

LOCATION: Elevation: 1460.15' Quadrangle: Cameron
District: Cameron County: Marshall
Latitude: 39.84432 Feet South of 39 Deg. 50 Min. 32.023 Sec.
Longitude: 80.53404 Feet West of 80 Deg. 30 Min. 00 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virginia Land Resources, Inc.</u>	Coal Operator	<u>West Virginia Land Resources, Inc.</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>Jay Hores</u>	Coal Operator	_____
Permit Issued Date	<u>10/08/25</u>	or Owner	_____

RECEIVED
Office of Oil and Gas

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Marshall ss:

JUL 20 2026

Matthew A Yearsley and John Campbell being first duly sworn according to law and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of May, 2026, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement with gas breaker	3147'	2423'	4 1/2" Casing 1475'	1610'
Expandable Cement	2423'	1485'	7" Casing 0'	1715'
Thixotropic with Green Dye	1485'	793'	9 5/8" Casing 0'	311'
Expandable Cement	793'	Surface	16" Conductor 10'	10'


Description of monument: 77" of 7" casing with company name, Well#, API# and date cemented. and that the work of plugging and filling said well was completed on the 18th day of May, 2026.

And further deponents saith not. Matthew A Yearsley

John Campbell

Sworn and subscribe before me this 6th day of July, 2026

My commission expires August 13, 2029 Kerrin A McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Strader Gopner Title: Oil & Gas Inspector

07/31/2026