

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
BONNIE WENDT
Lease or Property Owner
11037 WAYNESBURG PIKE CAMERON, WV 26033
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
MAJORSVILLE, WV-PA 7.5'
Well Location
WEBSTER
District
MARSHALL
County
MC-122 (Access)
Well No.
WENDT
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Jim Wickham

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
John G. Campbell and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 30th of January, 2020, Year and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Logged access hole from surface to bottom of 7" casing at 530". Attempted to remove 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Set 7" Packer at 500'. Cemented hole from 500' until cement was visible at the end of the laterals with 175 sacks of Lateral Cement. Pumped 1,780 gallons of total cement or 156% of the calculated volume. Removed 7" packer at 500'. Cemented from 500' to surface with 95 sacks of expanding cement. Cement did circulate at the surface. Left 530' of 7" casing from surface to 530'. Left 42' of 9 5/8" from surface to 42'.		7" Steel Casing	0'	530'
		9 5/8" Steel Casing	0'	42'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>(849' - 855')</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 31st of January, 2020

And further deponents saith not.

John G. Campbell

John G. Campbell
Matthew A. Yearsley


Matthew A. Yearsley

Sworn to and subscribed before me this 4th day of February, 2020

Richard O'Dell

Notary Public

My commission expires:
06/17/2021



Permit No. 47-051-01131
Well No. MC-122 (Access)
Latitude: 39° 52' 57.48"N
Longitude: 80° 36' 58.80"W