

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Hanson Operator Well No.: MC-47A

LOCATION: Elevation: 1387.05' Quadrangle: Cameron, WV, PA 7.5"
District: Cameron County: Marshall
Latitude: _____ Feet South of 39 Deg. 51 Min. 47.34 Sec.
Longitude: _____ Feet West of 80 Deg. 33 Min. 10.86 Sec.

Well Type: OIL _____ GAS X

Company Consolidation Coal Co Coal Operator 1 Bridge St
or Owner Monongah, WV 26554

Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 09/04/20

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Marshall ss:

David Vickers and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 24th day of August, 2020, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|-------------|------|------|--------------|------|
| Thixotropic | 515' | 465' | | |
| Expendable | 465' | 0' | | |
| 7" | 532' | 0' | 0' | 532' |
| 9 5/8" | 43' | 0' | 0' | 43' |
| | | | | |
| | | | | |

Description of monument: 7" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 27th day of August, 2020.

And further deponents saith not. David Vickers
Matthew A. Yearsley



Sworn and subscribe before me this 4th day of SEP, 2020

My commission expires: 09/15/22
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Jim Nicholson Title: Oil & Gas Inspector

08/06/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

DAVID L & CHRISTINA M. HANSON
Lease or Property Owner
790 DRAGON HWY. CAMERON, WV 26033
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

CAMERON WV, PA 7.5"
Well Location

CAMERON
District

MARSHALL
County

MC-47 (Access)
Well No.

HANSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Jim Wickham

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DAVID VICKERS and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24th day of August, 2020 and that the well was plugged in the following manner:

| Sand or Zone Record | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|---|------------------|--|---------------|----------------|
| Formation | | | | |
| Attempted to remove 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Set cast iron bridge plug at 515'. Cemented hole from 515' to 465' with 10 sacks of Thixotropic Cement. From 465' to the surface 135 sacks of Expandable Cement. Cement did circulate at the surface. Access hole continues on a curve from 532' until intersection with the production hole at coal seam. The bottom of the access hole is plugged back from the MC-47 production hole plugging. See MC-47 P Affidavit for details. Left 532' of 7" casing from surface to 532'. Left 43' of 9 5/8" from surface to 43'. | | | | |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | (948' - 954') | 77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |

... and that the work of plugging and filling said well was completed on the 27th day of August, 2020

And further deponents saith not.

David Vickers
David Vickers

Matthew A. Yearsley
Matthew A. Yearsley


Sworn to and subscribed before me this 4th day of SEP, 2020

Thomas J. Sullivan

Notary Public

My commission expires: 09/15/22

Permit No. 47-051-01136
Well No. MC-47 (Access)
Latitude: 39° 51' 47.34"N
Longitude: 80° 33' 10.86"W



08/06/2021