

COPY

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

MCELROY COAL COMPANY
Coal Operator or Owner
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Address

MCELROY COAL COMPANY
Name of Well Operator
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Complete Address

MCELROY COAL COMPANY
Coal Operator or Owner
6126 ENERGY DRIVE MOUNDSVILLE, WV 26041
Address

CAMERON, WV 7.5'
Well Location

JACK R. HAMMERS AND PAUL F. HAMMERS
Lease or Property Owner
165 OAKMONT ROAD, WHEELING, WV 26003
#3 SQUIRE VALLEY, BARBOURSVILLE, WV 26504
Address

CAMERON
District

MARSHALL
County

M-1594
Well No.

HAMMERS, JACK R. & PAUL F.
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Jana ...
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12th day of May, 2014 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 7/8" hole from the surface to 140'. Reduced hole to 9 7/8".		16" Casing	0'	20'
Cleaned 9 7/8" hole from 140' to 929'. Reduced hole to 6 1/4".		7" Casing	85"	Unknown
Cleaned 6 1/4" hole from 929' to 1855'. Tagged solid plug at 1855'.		10 1/2" Casing	0'	19'
Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 802' to 808'. Removed 85' of 7" casing from 929' to 1014'. Left an unknown amount of 7" casing in the hole from 1014' to an unknown depth. Cut remaining 7" casing at the following depths: 1850', 1750', 1650', 1550', 1450', 1350', 1250', 1150', and 1050'. Left 19' of 10 1/2" casing in the hole from 140' to 159'.				
Cemented hole from 1855' to the surface as follows:				
From 1855' to 1008' with 108 sacks of Expandable Cement. From 1008' to 702' with 155 sacks of Thixotropic Cement with Green Dye. From 702' to the Surface with 309 sacks of Expandable Cement. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	(802' - 808')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		

RECEIVED
Office of Oil and Gas
JUN 30 2014
WV Department of Environmental Protection

... and that the work of plugging and filling said well was completed on the 21st day of May, 2014.

And further deponents saith not.


Delbert Moore
Delbert Moore

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 13th day of June 2014

Kara Beth Forst
Notary Public

My commission expires: 11/4/23



Permit No. 47-51-01417-P
Well No. M-1594