

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

MCELROY COAL COMPANY
Coal Operator or Owner
RD #4, BOX 425 MOUNDSVILLE, WV 26041
Address

MCELROY COAL COMPANY
Coal Operator or Owner
RD #4, BOX 425 MOUNDSVILLE, WV 26041
Address

O.E & SARAH LOU BURGE
Lease or Property Owner
RD.3 BOX 33 CAMERON, WV 26033
Address

MCELROY COAL COMPANY
Name of Well Operator
RD #4, BOX 425 MOUNDSVILLE, WV 26041
Complete Address

CAMERON, WV 7.5'
Well Location

CAMERON
District

MARSHALL
County

M-1527
Well No.

BURGE, O.E & SARAH LOU
Farm

STATE INSPECTOR SUPERVISING PLUGGING U J T

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MARK WILSON and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 1st day of June, 2012 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 6 1/2" hole from the surface to 2673'. Tagged plug at 2673'. Cut existing 7" casing at the following depths; 2050', 1947', 1840', 1733', 1627', 1524' and 1400'. Cemented bottom hole from 2673' to 1924' with 145 sacks of Expandable Cement. Removed 1297' of 7" casing from surface to 1297'. Left 868' of 7" casing in the hole from 1297' to 2165'. Left 20' of 10 3/4" casing in the hole from 241' to 261'. Cleaned 6 1/2" hole from 1297' to top of bottom hole plug at 1924'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam (1075' - 1082'). Possible junk metal remaining through Pittsburgh Coal seam. Left 20' of 16" conductor pipe in the hole from 20' to surface.		16" Conductor	0'	20'
		10 3/4" Casing	0'	20'
		7" Casing	1297'	868'
Cemented hole from 2673' to surface as follows; From 2673' to 1924' with 145 sacks of Expandable Cement. From 1924' to 1282' Expandable Cement. From 1282' to 975' with 135 sacks of Thixotropic Cement with green dye. From 975' to surface with Expandable Cement. A total of 755 sacks of cement, 620 sacks of Expandable Cement and 135 sacks of Thixotropic Cement, were used to fill the hole from 2673' to surface. Cement did circulate at the surface.				
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	<u>(1075' - 1082')</u>	7" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of June, 2012

And further deponents saith not.


Mark Wilson
Mark Wilson

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 13th day of August, 2012

Jacqueline L. Shriver
Notary Public

My commission expires:
March 18, 2020



Permit No. 47-051-01456-P
Well No. M-1527

08/31/2012