

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Soloman McCracken Operator Well No.: M-1512

LOCATION: Elevation: 1331.21 Quadrangle: Cameron WV, PA  
District: Liberty County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 49 Min. 14.28 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 30.40 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 02/26/2020 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13th day of July, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	2544'	1130'		
Thixotropic Cement w/ Green Dye	1130'	830'		
Expandable Cement	830'	Surface		
7" Casing	1444'	2040'	1444'	596'
10 3/4" Casing	1044'	1317'	1044'	273'
24" Conductor	Surface	12'	0'	12'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 15th day of August, 2022.


And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 29 day of August, 2022

My commission expires: June 8, 2027

Christopher Andrew Willis  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Strader Gover 08/29/2022 Title: Oil & Gas Inspector

02/17/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

**CONSOLIDATION COAL COMPANY**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**CONSOLIDATION COAL COMPANY**  
Coal Operator or Owner  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Address  
**THOMAS BRIGGS ET UX**  
Lease or Property Owner  
**996 TUNNEL HILL RD. CAMERON, WV 26033**  
Address

**CONSOLIDATION COAL COMPANY**  
Name of Well Operator  
**1 BRIDGE STREET MONONGAH, WV 26554**  
Complete Address  
**CAMERON WV, PA**  
Well Location  
**LIBERTY**  
District  
**MARSHALL**  
County  
**M-1512**  
Well No.  
**SOLOMAN MCCRACKEN**  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower 08/29/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
**MATTHEW A. YEARSLEY** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 13<sup>th</sup> day of July, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 2 7/8" hole through the 7" casing from the surface to 2544'. Tagged a plug at 2544'. Cemented the bottom hole from 2544' back to 1951' with 110 sacks of Expandable Cement with a Gas Blocker additive. Tagged top of bottom hole plug at 1951'. Removed 1444' of 7" casing from the surface to 1444'. Attempted to remove remaining 7" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left 596' of 7" casing in hole from 1444' to 2040'. Cut the remaining 7" casing at 1636' and 1846'. Removed 1044' of 10 3/4" casing from the surface to 1044'. Attempts to remove the remaining 10 3/4" casing by pulling 150% of the string weight were unsuccessful. Left 273' of 10 3/4" casing in the hole from 1044' to 1317'. Cut the remaining 10 3/4" casing at 1080' and 1130'. Cleaned a 12 1/4" hole from the surface to the top of the remaining 10 3/4" casing at 1044'. Reduced the hole to 9 7/8" at 1044'. Cleaned a 9 7/8" hole from 1044' to the top of the remaining 7" casing at 1444'. Reduced the hole to 6 1/4" at 1444'. Cleaned a 6 1/4" hole from 1444' to the top of the bottom hole plug at 1951'. Cleaned a 12 1/4" hole through the Pittsburgh Coal Seam (923.8' - 930.2'). Left 12' of a 24" conductor in the hole from surface to 12'. <b>Cemented the hole from 1951' back to surface as follows:</b> From 1951' to 1130' with 195 sacks of Expandable Cement with a Gas Blocker additive and from 1130' to 830' with 225 sacks of Thixotropic Cement with Green Dye. Tagged top of Thixotropic Cement plug at 830'. Cemented the hole from 830' back to the surface with 505 sacks of Expandable Cement. Cement did circulate at the surface.	7" Casing	1444'	596'	
	10 3/4" Casing	1044'	273'	
	24" Conductor	0'	12'	
Coal Seams	Description of Monument			
<b>Pittsburgh</b>	923.8' - 930.2'			
	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 15<sup>th</sup> day of August, 2022

And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley


*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 29 day of August, 2022

*Christopher Andrew Willis* 02/17/2023  
Notary Public

My commission expires: June 8, 2027



Permit No. 47-051-02313  
Well No. M-1512  
Latitude: 39° 49' 14.28"N  
Longitude: -80° 32' 30.40"W