

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: L. Howard Operator Well No.: M-1502

LOCATION: Elevation: 1394' Quadrangle: Cameron WV, PA  
District: Cameron County: Marshall  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 49 Min. 23.18 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 33 Min. 07.74 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 12/12/2022 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1st day of March, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1280'	792'	8 5/8" Casing - 253'	Unknown - Multiple cuts placed in remaining casing
Expandable Cement	792'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 29th day of March, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 24 day of April, 2023

My commission expires: June 8, 2027  
Christopher Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Shadrach Gower Title: Inspector Oil & Gas

05/11/2023



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
GLEN PAUL COURTRIGHT ET AL  
Lease or Property Owner  
13 WILLARD LN. CAMERON, WV 26033  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
CAMERON WV, PA  
Well Location  
CAMERON  
District  
MARSHALL  
County  
M-1502  
Well No.  
L. Howard  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Shadrach Gower

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 1<sup>st</sup> day of March, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 278'. Cleaned a 9 7/8" hole from 278' to top of existing 8 5/8" casing at 398'. Cleaned a 7 7/8" hole from 398' to 1280'. Cleaned a 7 7/8" hole through Pittsburgh Coal Seam (993.5' - 1000.7'). Removed 253' of 8 5/8" casing from 398' to 651'. Attempts to remove remaining 8 5/8" casing from 651' by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 651' to an unknown depth. Cut remaining 8 5/8" casing at the following depths: 1201', 1151', 1101', 1050', 1011', 1006', 1003', 1000.7', 999.7', 998', 996.7', 995', 993.5', 992.5', 988', 983.5', 943.5', 893.5', and 821'. Left 20' of 16" conductor pipe in the hole from the surface to 20'. <b>Cemented the hole from 1280' back to the surface as follows:</b> From 1280' to 792' with 145 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 792'. Cemented the hole from 792' to the surface with 495 sacks of Expandable Cement. Cement did circulate at surface. A total of 640 sacks of cement were used to fill the hole from 1280' to the surface.	8 5/8" Casing  16" Conductor	253'  0'	Unknown  20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>993.5' - 1000.7'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 29<sup>th</sup> day of March, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley


Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 24 day of April, 2023

05/11/2023

My commission expires:

June 8, 2027



Christopher Willis  
Notary Public

Permit No. 47-051-02322  
Well No. M-1502  
Latitude: 39° 49' 23.18"N  
Longitude: -80° 33' 07.74"W