

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Mary Hughes Operator Well No.: M-1598

LOCATION: Elevation: 1154.8' Quadrangle: Cameron WV, PA  
District: Cameron County: Marshall  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 49 Min. 43.15 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 14.09 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 11/30/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 28th day of November, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1000'	538'	7" Casing - 17' Milled	Unknown
Expandable Cement	538'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 14th day of December, 2022.

And further deponents saith not. Matthew Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 30 day of December, 2022

My commission expires: June 8, 2027  
Christopher Andrew Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Trader Gower Title: Inspector Oil & Gas 05/11/2023



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
RICHARD D. SCOTT ET UX  
Lease or Property Owner  
798 GREEN VALLEY RD. CAMERON, WV 26033  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
CAMERON WV, PA  
Well Location  
CAMERON  
District  
MARSHALL  
County  
M-1598  
Well No.  
MARY HUGHES  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Shadrach Gower 12/30/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28<sup>th</sup> day of November, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 248'. Reduced the hole to 9 7/8" at 248'. Cleaned a 9 7/8" hole from 248' to the top of the existing 7" casing at 567'. Reduced the hole to 6 1/4" at 567'. Attempts to enter the 7" casing at 567' were unsuccessful. Milled 7" casing from 567' to 584'. A 2 <sup>nd</sup> attempt to enter the 7" casing at 584' was successful. Cleaned out the existing 7" casing from 584' to 1000'. Attempts to remove the 7" casing from 584' by pulling 150% of the string weight were unsuccessful. Left an unknown amount of 7" casing in the hole from 584' to an unknown depth. Cut the remaining 7" casing at the following depths: 956', 945', 895', 845', 795', 755', 750', 745.7', 744.7', 743.1', 741.5', 739.9', 738.2', 737.2', 733', 728', 722', 688' and 648'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (738.2' - 744.7'). Left 20' of 16' conductor pipe in the hole from the surface to 20'. <b>Cemented the hole from 1000' back to the surface as follows:</b> From 1000' to 538' with 105 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 538'. Cemented the hole from 538' to the surface with 280 sacks of Expandable Cement. Cement did circulate at surface. A total of 385 sacks of cement were used to fill the hole from 1000' to the surface.	7" Casing  16" Conductor	17' Milled  0'	Unknown  20'
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	738.2' - 744.7'			
	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 14<sup>th</sup> day of December, 2022

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright 05/11/2023

Sworn to and subscribed before me this 30 day of December, 2022

Christopher Andrew Willis  
Notary Public

My commission expires: June 8, 2027

Permit No. 47-051-02420  
Well No. M-1598  
Latitude: 39° 49' 43.15"N  
Longitude: -80° 32' 14.09"W