

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Earnest Wendt Operator Well No.: M-1787

LOCATION: Elevation: 1430' Quadrangle: Cameron WV, PA
District: Liberty County: Marshall
Latitude: 39.79648 Feet South of 39 Deg. 47 Min. 47.3495 Sec.
Longitude: -80.52158 Feet West of -80 Deg. 31 Min. 17.7238 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources INC. Coal Operator West Virginia Land Resources INC.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent Jay Hores Coal Operator _____
Permit Issued Date 7/17/2023 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Marshall ss:

Mathew A. Yearsley and Mark Wilson being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 24th day of July, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic Cement with Green Dye	1510'	954'	8 5/8" Casing - 1558'	296'
Expandable Cement	954'	Surface	16" Conductor Casing - 20'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 7th day of August, 2024.

And further deponents saith not. Matthew A. Yearsley
Mark Wilson



Sworn and subscribe before me this 23rd day of August, 2024

My commission expires: June 8, 2027

Christy Strader
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Strader Gower 08/23/2024 Title: Oil & Gas Inspector

09/13/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ANDREW L. & DANA L. SCHRACK
Lease or Property Owner
2008 Hupp Ridge RD. Cameron, WV 26033
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Cameron WV
Well Location
Liberty
District
Marshall
County
M-1787
Well No.
Earnest Wendt
Farm

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower ~~Strader Gower~~
AFFIDAVIT 08/23/2024

STATE OF WEST VIRGINIA,
County of Marshall ss:
MATTHEW A. YEARSLEY and Mark Wilson being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24th day of July, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from surface to 365'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 365' to 1262'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam (1154' - 1161') Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1262' to 1510'. Removed 1262' of 8 5/8" casing from surface to 1262'. A diligent effort was made to remove remaining 8 5/8" from 1262' to 1558' by pulling 150% of the string weight. All attempts were unsuccessful. Cut remaining 8 5/8" casing at 1486', 1382', 1361', and 1311'. Left 296' of 8 5/8" casing in hole from 1262' to 1558'. Left 20' of 16" Conductor Casing in hole from surface to 20'. <u>Cemented hole from 1510' to surface as follows:</u> Cemented from 1510' to 954' with 235 sacks of thixotropic cement with green dye and gas blocker. Cemented from 954' to surface with 445 sacks of expanding cement. Cement did circulate at surface. A total of 680 sacks of cement were used to fill hole from 1510' to surface.	8 5/8" Casing 16" Conductor Casing	1262' 0'	296' 20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1154'-1161'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of August, 2024

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley

Mark Wilson
Mark Wilson

Sworn to and subscribed before me this 23rd day of August, 2024.

[Signature]
Notary Public

My commission expires:
June 8, 2027



Permit No. 47-051-02503
Well No. M-1787
Latitude: 39° 47' 47.34"N
Longitude: -80° 31' 17.72"W

09/13/2024