


Cameron dist



30060

Cameron District, Marshall County, W. Va.
By The Manufacturers Light & Heat Co., 800 Union Trust Bldg.,
Pittsburgh, Pa.

On 40 acres, surface owned by Margaret J. Frye, Star Route,
Cameron, W. Va., and mineral rights by ML&C Co., Pgh., Pa.

Drilled prior to June 1, 1929.

Elevation, 1463'.

16" conductor; 10" casing, 922'; 8 1/2", 1395'; 6-5/8", 2165'.

Coal was encountered at 615-618, 805-811, 902-912, and 1440-1445'.


Abandonment reported to Dept. of Mines August 20, 1936, & 8-11-36.

Gas well.

MARS-60-A

	Top.	Bottom.	Thickness.
Waynesburg Coal	615	- 618	3
Mapletown (Sewickley) Coal	805	- 811	6
Pittsburgh Coal	902	- 912	10
Murphy Sand	1050	- 1100	50
Cow Run Sand (Moundsville)	1220	- 1245	25
Little Dunkard Sand	1280	- 1334	54
Big Dunkard Sand	1385	- 1440	55
Freesport Coal	1440	- 1445	5
First Salt Sand	1730	- 1780	50
Second Salt Sand	1805	- 1855	50
Little Linn	1940	- 1950	10
Pencil Cave	1950	- 1970	20
Big Linn	1970	- 2040	70
Big Injun Sand (break at 2140-2160') (gas at 2104')	2040	- 2285	245
Pink rock	2760	- 2780	20
Fifty-foot Sand (gas at 2817', SIM)	2817	- 2837	20
Gordon Sand	2867	- 2897	30
Fourth Sand	2897	- 2901	4
Slate and sand shells	2901	- 3013	112
Total depth		3013	

Liberty District, Marshall County, W. Va.
 By Manufacturers Light & Heat Co.
 Completed Jan. 4, 1929.
 Record from Mr. Schillhahn Sept. 30, 1939.
 Abandoned.



	Top.	Bottom.
Pittsburgh Coal	902	- 912
Murphy Sand	1050	- 1100
Little Dunkard Sand	1280	- 1334
Big Dunkard Sand	1385	- 1440
Freeport Coal	1440	- 1445
1st Salt Sand	1730	- 1780
2nd Salt Sand	1805	- 1855
Little Lime	1940	- 1950
Big Lime	1970	- 2040
Big Injun Sand (break, 2140-2160')	2040	- 2285
50-Foot Sand (gas, 2817')	2817	- 2839
Gordon Sand	2867	- 2897
4th Sand	2897	- 2901
Total depth		3013