



04 09 03:02p  
 JUN. 9. 2009 10:10AM  
 Rev (5-01)  
 WR-38  
 DATE: 05-01-2009

tristan jenkins  
 CALL FEDERAL RV 2

3046220180

P-1

API # 47-061-0105P

61-00105P

STATE OF WEST VIRGINIA  
 DEPARTMENT OF ENVIRONMENTAL PROTECTION  
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

RECEIVED  
 Office of Oil & Gas  
 JUN 12 2012  
 WV Department of  
 Environmental Protection

Farm name: Wilson, D. - Estate Operator Well No. E2-534  
 LOCATION: Elevation: 1,498' Quadrangle: Blacksville  
 District: Clay County: Monongalia  
 Latitude: 2098 Feet South of 39 Deg. 40 Min. 00 Sec.  
 Longitude: 3 Feet West of 80 Deg. 15 Min. 00 Sec.  
 Well Type: OIL  GAS  X   
 Company: Eastern Associated Coal LLC Coal Operator Eastern Associated Coal LLC  
 or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570  
 Agent: Edward Y. Hoy Coal Operator   
 or Owner   
 Permit Issued Date: Oct 24, 2007

AFFIDAVIT

STATE OF WEST VIRGINIA,  
 County of Monongalia ss:

William C. Chisler and James D. Stieringer being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 3<sup>rd</sup> day of March, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Pulled out 3240' of 2" casing. Then pulled out 2135' of 7" casing. There is 483' of 7" casing left in the hole. Shot off and pulled out 1354' of 8" and there is 775' of 8" left in the hole. There is 1185' of 10" still in the hole.				
Cleaned with an 8" bit down to 2130'.				
Logged the hole with Century Wireline Service. Coal seam 1162' to 1167' based on log information. The hole deviated 57.6 feet at the coal seam. (9 feet South and 56.92 feet East)				
Slotted 7", 8", and 10" pipe at 50' intervals				
Ran 1-1/2" tubing and pumped the bottom plug with 160 sacks of cement and 55 sacks of ETK expanding cement.				
Then ran 1309' of 4-1/2" tubing and pumped the top plug with 500 sacks of ETK expanding cement. Swabbed water off and rig down. Plug at 1280'.				


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 16<sup>th</sup> day of April, 2009.

And further deponents saith not. William Chisler

James D. Stieringer

Sworn and subscribe before me this 12 day of May, 2009

My commission expires: Nov. 03, 2018  
Crystal J. Speaks  
 Notary Public



Oil and Gas Inspector: [Signature]