

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Michael Godby Operator Well No.: F2-449

LOCATION: Elevation: 1,496 Quadrangle: Wadestown  
District: Battelle County: Monongalia  
Latitude: 4,300 Feet South of 39 Deg. 40 Min. 00 Sec.  
Longitude: 7,700 Feet West of 80 Deg. 17 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp Coal Operator: Eastern Associated Coal Corp  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator: \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date: December 11, 2001

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:


Jeff Tennant and Jeff Hostuttler being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 6<sup>th</sup> day of December, 2001, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Pulled rods/Pulled 2" tubing/Ran 1 1/2" tubing to 3,214'. Pumped bottom plug with 1 sack of gel and 75 sacks of cement.				
Pulled 2,224' of 5" pipe, pulled 1,755' of 7" pipe.				
Ripped 8" pipe from 1,240' to 1,310'.				
Ran logs with Timco (gamma-neutron and caliper) and Sperry Sun (directional survey).				
Ran 1 1/2" tubing and pumped 1 sack gel and 130 sacks cement. Pulled 8" pipe in two.				
Ran 1,420' of 4 1/2" pipe and pumped 105 E1K cement and 330 sacks of Portland cement.				
Swabbed off and checked latch down plug @ 1,400'				
Pittsburgh Coal: 1,282 - 1,290				

Description of monument: 4 1/2" Pipe with metal plate, API#, Date plugged and that the work of plugging and filling said well was completed on the 21<sup>st</sup> day of January 2002.

And further deponents saith not.


x Jeff Tennant  
x Jeffery A. Hostuttler



Sworn and subscribe before me this 27<sup>th</sup> day of February 2002  
My commission expires: September 18, 2004

Mark Allen Gouzd  
Notary Public

Oil and Gas Inspector: [Signature]



MOND 0502P